

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-02812500-01 0001
Spot: SWNENESW Sec/Twnshp/Rge: 9-9S-23W
2287 feet from S Section Line, 3110 feet from E Section Line
Lease Name: BRUSH CREEK Well #: 401W
County: GRAHAM Total Vertical Depth: 3893 feet

Operator License No.: 5088
Op Name: DARRAH, JOHN JAY, JR.
Address: 225 N MARKET STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PKR		3588		
PROD	5.5	3893		125 SX
SURF	8.625	209		175 SX
TI	2.375	3588		

Well Type: EOR UIC Docket No: E15497.5 Date/Time to Plug: 11/30/2012 12:00 PM
Plug Co. License No.: 34723 Plug Co. Name: INFINITY WELL SERVICES, LLC
Proposal Rcvd. from: WILL DARRAH Company: JOHN JAY DERRAH JR. Phone: (316) 219-3390

Proposed Plugging Method: Ordered 500 sx 60/40 pozmix 4% gel cement w/700-800 # hulls.
Injection zone: 3722' - 3724' and 3750' - 3753'.
Perforated at 2375', 2015', 1175' and 205'.

Plugging Proposal Received By: MARVIN MILLS WitnessType: NONE
Date/Time Plugging Completed: 11/30/2012 5:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perforated at 2375', 2015', 1175' and 205'.
Ran tubing to 3700' and pumped 100 sx cement w/200 # hulls.
Pulled tubing to 2850' and pumped 100 sx cement w/200 # hulls.
Pulled tubing to 1900' and pumped 240 sx cement to circulate to surface of 5 1/2" casing and 8 5/8" x 5 1/2" annulus.
Pulled all tubing and topped off 5 1/2" casing w/35 sx cement.

GPS: 39.28350 -099.89507

Perfs:

Top	Bot	Thru	Comments
3750	3753		
3722	3724		

Remarks: SOS TICKET # 651

Plugged through: TBG

District: 04

Signed

Pat Bedore
(TECHNICIAN)

CM

DEC 07 2012

Form CP-2/3