

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-01547-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 9-9S-23W
2310 feet from S Section Line, 2310 feet from E Section Line
Lease Name: BRUSH CREEK UNIT Well #: 501
County: GRAHAM Total Vertical Depth: 3871 feet

Operator License No.: 5088
Op Name: DARRAH, JOHN JAY, JR.
Address: 225 N MARKET STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3905		125 SX
SURF	8.625	246		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/29/2012 11:00 AM
Plug Co. License No.: 34723 Plug Co. Name: INFINITY WELL SERVICES, LLC
Proposal Rcvd. from: WILL DARRAH Company: JOHN JAY DARRAH JR. Phone: (316) 219-3390

Proposed Plugging Method: Ordered 500 sx 60/40 pozmix 4% gel cement w/700-800# hulls.
Tools stuck in hole at 3750'.
DV tool at 1900'. Circulated with black magic.
Perforations at 2375', 2015', 1175' and 250'.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/29/2012 3:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perforated at 2375', 2015', 1175' and 250'.
Ran tubing to 3700' and pumped 100 sx cement w/200 # hulls.
Pulled tubing to 2850' and pumped 100 sx cement w/200 # hulls.
Pulled tubing to 1900' and pumped 260 sx cement to circulate to surface of 5 1/2" casing and 8 5/8" x 5 1/2" annulus.
Pulled all tuing and topped off 5 1/2" casing w/35 sx cement.

GPS: 39.28348 -099.89275

Perfs:

Top	Bot	Thru	Comments
3702	3873		

Remarks: SOS TICKET # 650

Plugged through: TBG

RECEIVED
DEC 11 2012
KCC WICHITA

District: 04

Signed Pat Bedore
12/12/12 (TECHNICIAN)

CM