

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-137-00525-00-00
Spot: W2NE Sec/Twnshp/Rge: 36-3S-24W
1320 feet from N Section Line, 1980 feet from E Section Line
Lease Name: STAPLETON Well #: 6
County: NORTON Total Vertical Depth: 3762 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: 370 W WICHITA AVE PO BOX 352
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3749		75 SX
SURF	8.625	280		125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/04/2012 9:30 AM
Plug Co. License No.: 5135 Plug Co. Name: FARMER, JOHN O., INC.
Proposal Rcvd. from: DUANE EICHMAN Company: FARMER, JOHN O., INC. Phone: (785) 483-8355

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/700 # hulls and 11 sx gel.
Production perforations: 3749' - 3762'.
Casing leak: 1400' - 1600'.
Perforated at 2050' and 275'.

Plugging Proposal Received By: PAT BEDORE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/04/2012 2:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perforated at 2050' and 275'.
Ran tubing to 3700' and pumped 11 sx gel followed by 50 sx cement w/100 # hulls.
Pulled tubing to 2050' and pumped 150 sx cement w/300 # hulls.
Pulled tubing to 1375' and pumped 50 sx cement to circulate to surface.
Pulled all tubing. Hooked to 5 1/2" casing and pumped 10 sx cement. Shut in pressure 300 psi.
Hooked to 8 5/8"x5 1/2" annulus and pumped 5 sx cement. Shut in pressure 200 psi.

Perfs:

Top	Bot	Thru	Comments
3749	3762		

RECEIVED
DEC 11 2012

Remarks: QUALITY OILWELL CEMENTING TICKET # 6107

KCC WICHITA

Plugged through: TBG

District: 04

Signed

Pat Bedore
12/11/12
(TECHNICIAN)

CM

DEC 6 2012