

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-20651-00-00
Spot: SWNESWNW Sec/Twnshp/Rge: 19-4S-18W
1920 feet from N Section Line, 740 feet from W Section Line
Lease Name: SUTLEY A Well #: 1
County: PHILLIPS Total Vertical Depth: 3635 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: 370 W WICHITA AVE PO BOX 352
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PC		1480		
PROD	5.5	3629		145 SX
SURF	8.625	232		150 SX
T1	2.375	3592		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/04/2012 3:00 PM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: DUANE EICHMAN Company: JOHN O FARMER INC. Phone: (785) 483-8355

Proposed Plugging Method: Ordered 250 sx 60/40 pozmix 4% gel cement w/300 # hulls and 13 sx gel.
Port Collar at 1480'. CWC w/165 sx.
Production perforations: 3200' - 3206'.

Plugging Proposal Received By: PAT BEDORE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/04/2012 4:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Hooked to 8 5/8" x 5 1/2" annulus and pressured up immediately.
Hooked to 5 1/2" casing and pumped 50 sx cement w/100 # hulls followed by 13 sx gel followed by 150 sx cement w/200 # hulls. Shut in.

GPS: 39.69250 -099.40051

Perfs:

Top	Bot	Thru	Comments
3200	3206		

RECEIVED
DEC 11 2012
KCC WICHITA

Remarks: QUALITY OILWELL CEMENTING TICKET # 6108

Plugged through: CSG

District: 04

Signed

Pat Bedore
(TECHNICIAN)

CM

DEC 6 7 2012