

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22379-00-00
Spot: SWSWNSW Sec/Twnshp/Rge: 17-10S-19W
1369 feet from S Section Line, 3783 feet from E Section Line
Lease Name: BERLAND B Well #: 2-17
County: ROOKS Total Vertical Depth: 3871 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3871		200 SX
SURF	8.625	232		160 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/31/2012 1:15 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 567-8104

Proposed Plugging Method: Ordered 470 sx 60/40 pozmix 4% gel cement w/700 # hulls.
PBTD: 3836'.
Perfs: 3454' - 3456', 3488' - 3491', 3505' - 3508' and 3781' - 3784'.
DV @ 1666' w/400 sx cement. Circulated cement to surface.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/31/2012 5:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Ran in hole with tubing to 3790'. Rigged to tubing and pumped 190 sx cement w/300 # hulls.
Pulled tubing to 2013'. Rigged to tubing and pumped 190 sx cement w/300 # hulls to circulated cement to surface.
Pulled tubing. Topped off 5 1/2" casing with 15 sx cement. Hole standing full.
Rigged to 8 5/8" casing and pumped 5 sx cement to pressure with 300 psi. Shut in pressure 300 psi.

GPS: 39.17999, -09946974

Perfs:

Top	Bot	Thru	Comments
3781	3784		
3505	3508		
3488	3491		
3454	3456		

Remarks: SWIFT SERVICES

Plugged through: TBG

RECEIVED
NOV 07 2012
KCC WICHITA

District: 04

Signed


(TECHNICIAN)

CM

NOV 09 2012