

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-075-20186-00-00
Spot: SWNESESE Sec/Twnshp/Rge: 30-23S-41W
706 feet from S Section Line, 648 feet from E Section Line
Lease Name: HCU (BONNIE 1) Well #: 3031
County: HAMILTON Total Vertical Depth: 2375 feet

Operator License No.: 33999
Op Name: LINN OPERATING, INC.
Address: 600 TRAVIS STE 5100
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2375	0	WITH 450 SX CMT
SURF	8.625	344		WITH 275 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/05/2012 3:30 PM
Plug Co. License No.: 34271 Plug Co. Name: KIVETT PLUGGING & PIPE PULLING, INC.
Proposal Revd. from: KENNETH KIVETT Company: KIVETT PLUGGING & PIPE PULLI Phone: (580) 363-3036

Proposed Plugging Method: PUMP DOWN 4 1/2" CASING 200# HULLS & 150 SX CMT. PRESSURE TO 500#. BRING 75 SX CMT EXTRA FOR ANNULUS.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/05/2012 5:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

FILL CASING WITH CMT FROM 2352' TO 0' USING 150 SX CMT & 150# HULLS. PRESSURE TO 500#. HOLDING AT 300#. PUMP 30 SX CMT DOWN THE ANNULUS TO 300#.

Perfs:

Top	Bot	Thru	Comments
2340	2352		

RECEIVED
NOV 27 2012
KCC WICHITA

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

District: 01

Signed

Ken Jehlik
11/08/12 (TECHNICIAN)

RECEIVED
NOV - 9 2012
KCC DODGE CITY