

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-19102-00-00
Spot: NENWSW Sec/Twnshp/Rge: 19-21S-11W
2310 feet from S Section Line, 4290 feet from E Section Line
Lease Name: SMITH A Well #: 1
County: STAFFORD Total Vertical Depth: 3630 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|-----------------|
| CIBP | | 3131 | | WITH 2 SX CMT |
| CIBP | | 3257 | | |
| PROD | 5.5 | 3629 | 0 | WITH 150 SX CMT |
| SURF | 8.625 | 252 | | WITH 150 SX CMT |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/15/2012 12:00 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: KEVIN WILES SR Company: AMERICAN WARRIOR Phone: (620) 275-2963

Proposed Plugging Method: CIBP @ 3131' WITH 2 SX CMT. PERFORATE @ 600' CIRCULATE TO 0'.

Plugging Proposal Received By: DANIEL BERNASCONI WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/15/2012 2:25 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET CIBP @ 3131' & PUT 2 SX CMT ON TOP WITH DUMP BAILER. PERFORATED 5 1/2" @ 600'. RAN TBG TO 604'. PUMPED 199 SX CMT DOWN THE TBG CIRCULATING CMT TO SURFACE UP 5 1/2" & 8 5/8" X 5 1/2" ANNULUS. PULLED TBG OUT OF HOLE. TOPPED HOLE OFF WITH 21 SX CMT.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3181 | 3239 | | |

RECEIVED
NOV 27 2012
KCC WICHITA

Remarks: **COMPLIANCE ISSUE: DENIED TA 10 YR RULE** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed

Richard M. Lacey
11/28/12 (TECHNICIAN)

RECEIVED
NOV 19 2012
KCC DODGE CITY