

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-075-20589-00-00
Spot: SESENWSE Sec/Twnshp/Rge: 20-22S-41W
1358 feet from S Section Line, 1331 feet from E Section Line
Lease Name: HCU Well #: 2021-B
County: HAMILTON Total Vertical Depth: 2904 feet

Operator License No.: 33999
Op Name: LINN OPERATING, INC.
Address: 600 TRAVIS STE 5100
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2864	0	WITH 475 SX CMT
SURF	8.625	246		WITH 180 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/12/2012 12:15 PM
Plug Co. License No.: 34271 Plug Co. Name: KIVETT PLUGGING & PIPE PULLING, INC.
Proposal Rcvd. from: KENNETH KIVET Company: KIVETT PLUGGING & PIPE PULLI Phone: (580) 363-3036

Proposed Plugging Method: PUMP DOWN 4 1/2" CASING 200# HULLS & 170 SX CMT. BRING 75 SX CMT FOR ANNULUS.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/12/2012 2:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

FILL 4 1/2" CASING WITH CMT FROM 2663' TO 0' USING 200 SX CMT & 200# HULLS. PRESSURE TO 500#. HOLDING AT 400#. PUMP 10 SX CMT DOWN THE ANNULUS TO 400#. HOLDING.

Perfs:

Top	Bot	Thru	Comments
2643	2663		

RECEIVED
NOV 27 2012
KCC WICHITA

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

District: 01

Signed


(TECHNICIAN)

RECEIVED

NOV 20 2012

KCC DODGE CITY

AWY