

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-21954-00-00
Spot: SWNESE Sec/Twnshp/Rge: 34-30S-12W
1756 feet from S Section Line, 817 feet from E Section Line
Lease Name: HAAS Well #: 9
County: BARBER Total Vertical Depth: 4490 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP	4.5	4130		WITH 2 SX CMT
COND	12.25	34		
PROD	4.5	4488	0	WITH 150 SX CMT
SURF	8.625	260		WITH 200 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/25/2012 1:00 PM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: ALAN VRATIL Company: VRATIL SERVICES Phone: (620) 886-2419

Proposed Plugging Method: SET CIBP @ 4130' & 2 SX CMT. LOAD & TEST CASING. IF HOLDS, PERFORATE 4 1/2" CASING AT 600'. PUMP DOWN CASING WITH CMT FILLING 4 1/2" CASING & 4 1/2" X 8 5/8" ANNULUS WITH CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/25/2012 1:35 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4130' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. PERFORATE 4 1/2" CASING @ 600'. LOAD CASING & PRESSURE TEST. HELD. PUMPED DOWN 4 1/2" CASING WITH 200 SX CMT, FILLING 4 1/2" CASING & 4 1/2" X 8 5/8" ANNULUS WITH CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4180	4182		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

RECEIVED
NOV 09 2012
KCC WICHITA

District: 01

RECEIVED

OCT 31 2012

KCC DOUGHE CITY

Signed

Stephen Pfeifer
(TECHNICIAN)