

1 040549

6-27

256

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 19- 033-20,671 0000

SW SW, SEC. 36, T 33 S, R 20 W/EX R

660 feet from S section line

4620 feet from E section line

Lease Name Ralph Baker Well # 5

County Comanche 157.62

Well Total Depth 4850 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 688

TECHNICIAN'S PLUGGING REPORT

Operator License # 6528

Operator: R.J. Patrick Operating Co.

Name:

Address P.O. Box 1314

Liberal, KS 67905-1314

Abandoned Oil Well Gas Well Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Midwest Casing Pulling License Number 6497

Address P.O. Box F, Sublette, KS 67877

Company to plug at: Hour: 10:30 a.m. Day: 27 Month: 6 Year: 19 91

Plugging proposal received from Ed Eves

(company name) Midwest Casing Pulling (phone) 316-675-8349

were: 4 1/2" drill pipe at 4835' w/125 sx cement, Perfs at 4759-4813'

1st plug pump 2 sx hulls and 20 sx cement over perfs,

2nd plug at 950' with 40 sx cement,

3rd plug at 700' with 50 sx cement,

4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 4:30 p.m. Day: 27 Month: 6 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug pumped down 4 1/2" with 200 lbs. hulls and 20 sx cement.

Went on vacuum-pumped down 4 1/2" with another 200 lbs. hulls and 20 sx cement. Total

bottom plug = 400 lbs. hulls and 40 sx common cement.

RECEIVED STATE CORPORATION COMMISSION

Spotted plugs through 4 1/2" pipe: 2nd plug at 950' with 40 sx cement,

JUL 02 1991

3rd plug at 700' with 50 sx cement,

4th plug at 40' with 10 sx cement.

CONSERVATION DIVISION Wichita, Kansas

Remarks: Used common cement by Midwest Casing Pulling. Recovered 3100' of 4 1/2" drill pipe.

(if additional description is necessary, use BACK of this form.)

INVOICED

(XXXXXX) observe this plugging.

DATE 7-18-91

Signed Stephen J. Pifer (TECHNICIAN)

INV. NO. 32289