

To: 041310 7-6
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-033-20,958 DDDO
100' W. OF
NW1/4 SEC. 5, T. 31 S, R. 17 W/X
2310 feet from S section line
5050 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License 131691
Operator: Coral Coast Petroleum LC
Name & Address: 200 E. First, Suite 201
Wichita, KS. 67202

Lease Home West Well 1
County Comanche 186.10
Well Total Depth 5726 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1019

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Clarke Corp. License Number 5105
Address 107 West Fowler, Medicine Lodge, KS. 67104

Company to plug at: Hour: 3:30 P.M. Day: 6 Month: 7 Year: 1998

Plugging proposal received from Alan Vratil
(company name) Clarke Corp. (phone) 316-886-5665

core: 5 1/2" @ 5686' w/ 215 sx. cement, PBD @ 5652', Perfs @ 4878-4882' + 5028'-5092',
1st plug set CIBP @ 4800' + put two sx. cement on top of CIBP
2nd plug spot 50 sx. cement @ 1069'
3rd plug spot 30 sx. cement @ 540
4th plug spot 10 sx. cement @ 40'

RECEIVED
STATE CORPORATION COMMISSION
JUL 11 1998
07-10-98
WICHITA, KANSAS

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 4:30 P.M. Day: 6 Month: 7 Year: 1998

ACTUAL PLUGGING REPORT 1st plug set CIBP @ 4800' + put 2 sx. cement on top of CIBP through bailer
2nd plug loaded hole w/ gel + spotted 50 sx. cement @ 1067'
3rd plug spotted 30 sx. cement @ 538'
4th plug spotted 20 sx. cement @ 60'

Remarks: Used 60/40 poz 6" gel by Allied. Recovered 2583' of 5 1/2" casing
Additional description is necessary, use BACK of this form.)

DATE (Date of observation) observe this plugging.

INVOICE NO. 50900

Signed Steve Durrant (TECHNICIAN)