

1 060856

2352

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 025-20,901 0000
NW SE SE, SEC. 10, T 32 S, R 22 W/E

990 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6033

Lease Name Thomas-Comstock Well # 1-10

Operator: Murfin Drilling Company
Name & Address: 250 North Water, Suite 300
Wichita, KS 67202

County Clark 219.05

Well Total Depth 6740 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 683

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 12:30 am Day: 23 Month: June Year: 19 86

Plugging proposal received from Bill Fulls

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" at 6740' PBTD 6585' Perfs at 6562-70'

1st plug sand back to 6520' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:15 pm Day: 23 Month: June Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 6520' and dumped 5 sx cement on top of sand through bailer, 2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 150 sx cement.

Maximum pressure 500 psi and shut in 200 psi

Remarks: Recovered 4800' 5 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE JUL 10 1986

INV NO. 14326

STATE CORPORATION COMMISSION signed Paul A. Luthi (TECHNICIAN)

07-08-86
JUL - 8 1986