

1091048

TO: STATE CORPORATION COMMISSION

API NUMBER 15-025-21,123 ood  
APP. C W/2 W/2 SEC. 10, T 32, S, R 22 W

CONSERVATION DIVISION - PLUGGING SECTION 2600 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 500 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME THOMAS-COMSTOCK WELL # 10-12

TECHNICIAN'S PLUGGING REPORT

COUNTY CLARK 274.25

OPERATOR LICENSE # 3882 5/4

WELL TOTAL DEPTH 6900 FEET

OPERATOR: SAMUEL GARY JR & ASSOC. PRODUCTION CSG: SIZE 5 1/2" @ 6580' WITH 150 SX

NAME AND 1670 BROADWAY, SUITE 3300 SURFACE CASING: SIZE 8 5/8" @ 700' WITH 430 SX

ADDRESS DENVER, CO 80202-4838 CONDUCTOR CSG: SIZE 20" @ 40'

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SWD WELL  D/A  Dual well - per Michelle in Dist. 1

OTHER WELL AS HEREINAFTER INDICATED \_\_\_\_\_

PLUGGING CONTRACTOR PRATT WELL SERVICE, INC LICENSE NUMBER 5893

ADDRESS PO BOX 847, PRATT, KS 67124

COMPANY TO PLUG AT: HOUR: 9:45 AM DAY: 25 MONTH: 04 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM TOM LARSON

RECEIVED  
STATE CORPORATION COMMISSION

(COMPANY NAME) PRATT WELL SERVICE (PHONE) 316-672-2531 MAY 15 2000

WERE: OPEN HOLE AT 6580-6900

CONSERVATION DIVISION  
Wichita, Kansas

SET CIBP @ 6375' WITH 5 SX CEMENT. PUMPED 300# HULLS - 10 SX GEL - 50 SX CEMENT - 10 SX

GEL - 100# HULLS - WIPER PLUG AND 150 SX CEMENT DOWN 8 5/8" CASING.

PLUGGING PROPOSAL RECEIVED BY SCOTT ALBERG

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL  PART  NONE

OPERATIONS COMPLETED: HOUR: 10:30 AM DAY: 04 MONTH: 05 YEAR: 2000

ACTUAL PLUGGING REPORT \_\_\_\_\_

SET CIBP @ 6375' WITH 5 SX CEMENT. PUMPED 300# HULLS - 10 SX GEL - 50 SX CEMENT - 10 SX

GEL - 100# HULLS - WIPER PLUG AND 150 SX CEMENT, <sup>down 8 5/8" casing.</sup> MAXIMUM PRESSURE 500#. SHUT IN PRESSURE

400#.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2190' OF 5 1/2" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

INVOICED

DATE 5/17/00 SIGNED \_\_\_\_\_

(TECHNICIAN)

FORM CP-2/3

INV. NO. 61732