


1 080282

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION SE NE SE
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-025-20,859 0000 

TECHNICIAN'S PLUGGING REPORT

1651 feet from (S) section line
331 feet from (E) section line

Operator License # 6029

Lease Name Patton Well # 2-3

Operator: Ladd Petroleum Corporation

County Clark

Name & Address P. O. Box 2848

Well Total Depth 5450 77.13 feet

Tulsa, OK 74101

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1405

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Eagle Drilling License Number 5380

Address 1150 First Oklahoma Tower, Oklahoma City, OK 73102

Company to plug at: Hour: 7:00 pm Day: 15 Month: December Year: 19 84

Plugging proposal received from Butch Steinert

(company name) Eagle (phone) 405-232-7834

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1450' with 50 sx cement

2nd plug at 700' with 40 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 10 sx cement

6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by I. H. Metz
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 9:00 pm Day: 15 Month: December Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1450' with 50 sx cement, 2nd plug at 700' with 40
sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface

with 10 sx cement, 5th plug to circulate rat hole with 10 sx cement, 6th plug to
circulate mouse hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Dowell
additional description is necessary, use BACK of this form.

INVOICED

DATE 12-26-84 I did not observe this plugging.

INV. NO. 6166

Signed J. A. Metz
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
DEC 17 1984
CONSERVATION DIVISION
Wichita, Kansas