

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-30108-00-00  
Spot: N2NWNW Sec/Twnshp/Rge: 28-16S-12W  
4950 feet from S Section Line, 4620 feet from E Section Line  
Lease Name: LAUDICK A Well #: 6  
County: BARTON Total Vertical Depth: 3380 feet

Operator License No.: 31086  
Op Name: RICHLAN DRILLING, A GENERAL PAR  
Address: 598 2ND AVE  
BEAVER, KS 67525

| String | Size  | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PKR    | 4.5   | 3250       |             |          |
| PROD   | 4.5   | 3378       |             | 25 SX    |
| SURF   | 8.625 | 333        |             | 200 SX   |

Well Type: OIL UIC Docket No: Date/Time to Plug: 10/23/2012 2:00 PM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Revd. from: RICK SCHREIBER Company: RICHLAN DRILING Phone: (620) 793-2032

Proposed  
Plugging  
Method:

Ordered 350 sx 60/40 pozmix 4% gel cement w/600 # hulls and 8 sx gel.

Plugging Proposal Received By: BRUCE RODIE  
Date/Time Plugging Completed: 10/23/2012 5:00 PM

WitnessType: COMPLETE (100%)  
KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1400', 825' and 300'.  
Ran tubing to 3300' and pumped 8 sx gel followed by 40 sx cement.  
Pulled tubing to 1450' and pumped 40 sx cement.  
Pulled tubing to 900'. Circulated cement with 40 sx cement.  
Pulled tubing to 300'. Circulated cement with 90 sx cement on casing and surface pipe.  
Topped off with 5 sx cement.

GPS: 38.63681 -098.66156

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 3378 | 3383 |      |          |

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

RECEIVED  
NOV 07 2012  
KCC WICHITA

District: 04

Signed Bruce Rodie  
10/27/12 (TECHNICIAN)

CM

NOV 29 2012