

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-119-21323-00-00  
Spot: SESESWNW Sec/Twnshp/Rge: 5-34S-28W  
2755 feet from S Section Line, 1101 feet from W Section Line  
Lease Name: VANDERPOOL Well #: 2-5  
County: MEADE Total Vertical Depth: 6400 feet

Operator License No.: 32211  
Op Name: O'BRIEN ENERGY RESOURCES CORP.  
Address: 18 CONGRESS ST, STE 207  
PORTSMOUTH, NH 03801

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	6385	2610	WITH 175 SX CMT
SURF	8.625	1488		WITH 550 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/09/2012 1:00 PM  
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.  
Proposal Rcvd. from: ROGER PEARSON Company: O'BRIEN ENERGY Phone: (580) 251-1881

Proposed Plugging Method: PLUG BOTTOM WITH 30 SX CMT & 200# HULLS. PLUG AT 1500' WITH 40 SX CMT. PLUG AT 600' WITH 40 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: NONE  
Date/Time Plugging Completed: 11/09/2012 4:30 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PLUG BOTTOM WITH 30 SX CMT & 100# HULLS. 1ST PLUG AT 1500' WITH 50 SX CMT. 2ND PLUG AT 600' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5680	5690		

Remarks: USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: CSG

District: 01

Signed: Richard M. Lacey  
11/29/12 (TECHNICIAN)

RECEIVED

NOV 19 2012

KCC DODGE CITY

RECEIVED  
NOV 27 2012  
KCC WICHITA

*KCC*