

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-21963-00-00
Spot: N2N2NE Sec/Twnshp/Rge: 35-32S-33W
390 feet from N Section Line, 1310 feet from E Section Line
Lease Name: COOPER I Well #: 1
County: SEWARD Total Vertical Depth: 5925 feet

Operator License No.: 5447
Op Name: OXY USA INC.
Address: 5 E GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5381		WITH 2 SX CMT
CIBP		5750		WITH 2 SX CMT
PROD 4.5		5917	2325	WITH 230 SX CMT
SURF 8.625		1596		WITH 700 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/01/2012 1:00 PM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: PARTIAL
Date/Time Plugging Completed: 11/02/2012 4:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 5381' WITH 2 SX CMT. LOAD HOLE WITH MUD, CUT CASING. 1ST PLUG AT 1640' WITH 50 SX CMT. 2ND PLUG AT 550' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5784	5792		
5610	5618		
5563	5568		
5537	5541		
5431	5438		


Remarks: USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: CSG

District: 01

RECEIVED
NOV - 9 2012
KCC DODGE CITY

Signed


(TECHNICIAN)

RECEIVED
NOV 14 2012
KCC WICHITA

AWD