

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-20469-00-00
Spot: SWNESWNW Sec/Twnshp/Rge: 20-33S-10W
3420 feet from S Section Line, 4453 feet from E Section Line
Lease Name: STEWART Well #: 1
County: BARBER Total Vertical Depth: 4700 feet

Operator License No.: 5039
Op Name: AGV CORP.
Address: PO BOX 377
ATTICA, KS 67009

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4699	2190	100 SX
SURF	8.625	352		275 SX

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 10/24/2012 11:00 AM

Plug Co. License No.: 34227 Plug Co. Name: AMERICAN WELL SERVICE LLC

Proposal Rcvd. from: DAVE MILLER Company: AGV Phone: (316) 215-1683

Proposed Plugging Method: SPOT 10 SX GEL & 50 SX CMT AT 3292'. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 380' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER

WitnessType: NONE

Date/Time Plugging Completed: 10/24/2012 12:15 PM

KCC Agent: STEVE PFEIFER

Actual Plugging Report:

TOP OF TBG FISH @ +/- 3300' UNABLE TO FISH RUN TBG TO 3292' & SPOT 10 SX GEL & 50 SX CMT. PULLED TBG UP & LET CMT SET. TAG TOP OF CMT @ 2290'. 1ST PLUG AT 610' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 390' WITH 50 SX CMT. 3RD PLUG AT 64' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4609	4630		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed: [Signature]
(TECHNICIAN)

RECEIVED

OCT 31 2012

KCC DODGE CITY

RECEIVED
NOV 09 2012
KCC WICHITA

ANY