

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-21952-00-00
Spot: NWSE Sec/Twnshp/Rge: 35-18S-21W
2006 feet from S Section Line, 1937 feet from E Section Line
Lease Name: BYERLEE Well #: 1
County: NESS Total Vertical Depth: 4179 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3955		WITH 2 SX CMT
PROD	4.5	4178	0	WITH 200 SX CMT
SURF	8.625	359		WITH 200 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/23/2012 3:00 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: SCOTT CORSAIR Company: AMERICAN WARRIOR Phone: (785) 398-1708

Proposed Plugging Method: RUN BOND LOG & CHECK FOR TOP OF CMT. RUN TBG TO 1700' & CIRCUALTE CMT TO SURFACE. TIE ONTO BACISDE & PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/23/2012 5:45 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

****PERFS AT 2213'-2216' & 2228'-2233' HAD BEEN CEMENTED WITH 150 SX CMT.****
SET CIBP @ 3955' WITH 2 SX CMT. RUN IN & TAGGED AT 1790'. RAN BOND LOG, FOUND CMT FROM 1450' TO 360'. RUN TBG TO 1700' & PUMPED 130 SX CMT. PULLED TBG & TOPPED OFF WITH 10 SX CMT. TIED ONTO BACKSIDE & PUMPED 5 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4103	4155		
2228	2233		
2213	2216		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

RECEIVED
NOV 09 2012
KCC WICHITA

District: 01

Signed Michael J. Maier
10/23/12 (TECHNICIAN)

RECEIVED

NOV 13 2012

KCC DOUGLAS CITY

Form CP-2/3

POW Y