

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-21879-00-00
Spot: NWSENW Sec/Twnshp/Rge: 19-20S-13W
3650 feet from S Section Line, 3630 feet from E Section Line
Lease Name: TITUS Well #: C 1
County: BARTON Total Vertical Depth: 3540 feet

Operator License No.: 33153
Op Name: KRIER, ROGER DBA KRIER OIL OPERA
Address: PO BOX 763
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3530		125 SX
SURF	8.625	325		250 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/01/2012 9:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: ROGER KRIER Company: KRIER OIL Phone: (620) 793-5925

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/01/2012 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Perforated at 1500', 775' and 325',
Ran tubing to 3400' and pumped 100 sx cement w/200 # hulls.
Pulled tubing to 1800' and pumped 100 sx cement w/200 # hulls.
Pulled tubing to 350' and circulated cement to surface with 50 sx cement and 100 # hulls.
Pulled tubing. Tied to surface pipe and pressured to 500 psi. Would not take cement.
Topped off casing with 5 sx cement.

Remarks: QUALITY OILWELL CEMENTING TICKET # 5400

Plugged through: CSG

District: 04

Signed Bruce Rodie
11/03/12 (TECHNICIAN)

CM

RECEIVED
NOV 13 2012
KCC WICHITA

NOV 02 2012