

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-22189-00-00
Spot: NWSWNWNW Sec/Twnshp/Rge: 27-22S-29W
830 feet from N Section Line, 235 feet from W Section Line
Lease Name: STEIMEL Well #: 1-27
County: FINNEY Total Vertical Depth: 4920 feet

Operator License No.: 5004
Op Name: VINCENT OIL CORPORATION
Address: 155 N MARKET STE 700
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	394		WITH 250 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/29/2012 7:30 AM
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.
Proposal Rcvd. from: MIKE GODFREY Company: DUKE DRILLING CO., INC. Phone: (316) 267-1331

Proposed Plugging Method: 1ST PLUG AT 1900' WITH 50 SX CMT. 2ND PLUG AT 1130' WITH 80 SX CMT. 3RD PLUG AT 600' WITH 40 SX CMT. 4TH PLUG AT 420' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: NONE
Date/Time Plugging Completed: 11/29/2012 11:00 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

Perfs:

1ST PLUG AT 1900' WITH 50 SX CMT. 2ND PLUG AT 1130' WITH 80 SX CMT. 3RD PLUG AT 600' WITH 40 SX CMT. 4TH PLUG AT 420' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

Signed Richard M. Lacey
12/12/12 (TECHNICIAN)

RECEIVED
DEC - 4 2012
KCC DODGE CITY

RECEIVED
DEC 06 2012
KCC WICHITA

Handwritten mark