

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-171-20911-00-00  
Spot: SWNESE Sec/Twnshp/Rge: 3-17S-34W  
2250 feet from S Section Line, 520 feet from E Section Line  
Lease Name: DECKER Well #: 1-3  
County: SCOTT Total Vertical Depth: 4860 feet

Operator License No.: 6113  
Op Name: LANDMARK RESOURCES, INC.  
Address: 1616 S VOSS RD STE 600  
HOUSTON, TX 77057

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	267		WITH 155 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/18/2012 1:30 PM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: ART CABECAS Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: 1ST PLUG AT 2470' WITH 50 SX CMT. 2ND PLUG AT 1530' WITH 80 SX CMT. 3RD PLUG AT 760' WITH 50 SX CMT. 4TH PLUG AT 300' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: NONE  
Date/Time Plugging Completed: 10/18/2012 3:30 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

Perfs:

1ST PLUG AT 2470' WITH 50 SX CMT. 2ND PLUG AT 1530' WITH 80 SX CMT. 3RD PLUG AT 760' WITH 50 SX CMT. 4TH PLUG AT 300' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

RECEIVED  
NOV 09 2012  
KCC WICHITA

District: 01

RECEIVED  
NOV - 5 2012  
KCC DODDGE CITY

Signed Richard Lacey  
11/22/12 (TECHNICIAN)

*Handwritten initials*