

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: ~~15-179-05161-00-04~~ 0004  
Spot: SENE SW Sec/Twnshp/Rge: 12-6S-27W  
1650 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: J.E. LEONARD Well #: 7  
County: SHERIDAN Total Vertical Depth: 3880 feet

Operator License No.: 6113  
Op Name: LANDMARK RESOURCES, INC.  
Address: 1616 S VOSS RD STE 600  
HOUSTON, TX 77057

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3880		200 SX
SURF	8.0625	200		175 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/30/2012 10:30 AM  
Plug Co. License No.: 4072 Plug Co. Name: PLAINS, INC  
Proposal Rcvd. from: BILL SCHMIDT Company: LANDMARK RESOURCES INC. Phone: (316) 772-0921

Proposed Plugging Method: Ordered 420 sx 60/40 pozmix 4% gel cement w/500 # hulls and 9 sx gel.  
8 5/8" surface casing set @ 200' w/175 sx cement. 5 1/2" casing set @ 3880 w/200 sx cement.  
TD 3880'. PBT 3879'. Perforations: 3620' - 3812'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/30/2012 7:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perforated production casing @ 2225', 1527' and 250'. Ran tubing to 3801.59'. Pumped 9 sx gel and followed with 80 sx cement w/200 # hulls.  
Pulled tubing to 2215.62'. Pumped 110 sx cement w/150 # hulls.  
Pulled tubing to 1123.82' and pumped 220 sx cement w/150 # hulls. Circulated cement to surface.  
Pulled tubing to surface. Pumped 10 sx cement. 5 1/2" and 8 5/8" surface casing full. Plug complete.

GPS: 39.54254N, -100.2844W

Perfs:

Top	Bot	Thru	Comments
3620	3812		

RECEIVED  
NOV 19 2012  
KCC WICHITA

Remarks: SOS CEMENT TICKET # 636

Plugged through: TBG

District: 04

Signed: Darrel Dipman  
11/27/12 (TECHNICIAN) *cm*

NOV 01 2012