

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-21730-00-01 0001
Spot: E2SW Sec/Twnshp/Rge: 2-27S-13W
1320 feet from S Section Line, 3285 feet from E Section Line
Lease Name: S AND S UNIT Well #: 2
County: PRATT Total Vertical Depth: 4248 feet

Operator License No.: 33810
Op Name: WALCHER OIL, LC
Address: 150 N MAIN STE 809
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3780		WITH 2 SX CMT
COND	13.375	242		WITH 325 SX CMT
PROD	5.5	4248	1818	WITH 160 SX CMT
SURF	8.625	1065		WITH 550 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/16/2012 4:15 PM
Plug Co. License No.: 34235 Plug Co. Name: AMIGOS WELL SERVICE INC.
Proposal Rcvd. from: EDGAR SANCHEZ Company: AMIGOS WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: CIBP @ 3780' & 2 SX CMT. PLUG AT 1100' WITH 15 SX GEL & 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: NONE
Date/Time Plugging Completed: 11/16/2012 6:15 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 3780' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 1100' WITH 15SX GEL & 50 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4173	4183		
4022	4027		
3830	3836		

RECEIVED
DEC 06 2012
KCC WICHITA

Remarks: **COMPLIANCE ISSUE: NOV TA LTR** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

RECEIVED
NOV 30 2012
KCC DODGE CITY

Signed Stephen J. Pfeifer
(TECHNICIAN)

RMS