

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:

Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

Hodgman County, Sec. 12 Twp. 22 Rge. 23 (E) (W)
Location as "NE/CNW/WSW" or footage from lines SW NE

Lease Owner Braden Deem, Inc.
Lease Name G. Miller B#1 Well No. _____
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 10/5/72 _____ 19____
Plugging completed 2/21/73 _____ 19____
Reason for abandonment of well or producing formation depleted.



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eves
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4563 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				9-5/8	257	none
				7"	4555	1786'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole, ran sand and 5 sacks cement. Loaded hole with water, shot pipe at 3380', spotted 60 barrels oil. Shot pipe at 2966', 2515', 2201', 2010', 1817', pulled 57 joints. Allied pumped 8 sacks gel, 70 sacks cement, 7 sacks gel and 50 sacks cement to plug well.

PLUGGING COMPLETE.

RCVP
08-29-72

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor VOTH CASING PULLING
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
WALTER VOTH (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Walter Voth
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of March, 19 73

My commission expires _____
MARGARET MELCHER
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires
Feb. 15, 1975

Margaret Melcher
Notary Public.

Sunray DX Oil Company
Tulsa, Oklahoma

Tulsa, Oklahoma
January 28, 1963

Contractor: Stickle Drilling Company
Date Commenced: January 10, 1963
Date Completed: January 24, 1963

Gustave Miller "B" No. 1
SW NE Section 12-22S-23W
Hodgeman County, Kansas

DRILLER'S LOG

Depth Figures Indicate Base of Formation:

Shale	1355
Shale and red bed	1884
Shale	2285
Lime	2715
Lime and shale	2720
Shale with lime	2790
Lime	2934
Shale and lime	3165
Lime and shale	3250
Shale and lime	3570
Lime and shale	3685
Shale and lime	3990
Lime and shale	4080
Lime	4570 TD
TD corrected by Electric Log	4572

RECEIVED
STATE CORPORATION COMMISSION

AUG 29 1972

CONSERVATION DIVISION
Wichita, Kansas

I, Fred E. Stickle, hereby certify the above to be a true and complete Driller's Log of Sunray DX Oil Company's Gustave Miller "B", Well No. 1, SW NE Section 12-22S-23W, Hodgeman County, Kansas.

Fred E. Stickle
FRED E. STICKLE

W. W. Sensley
Notary Public

My Commission expires:
January 11, 1967