

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Bldg.
 Wichita, Kansas 67202

Form CP-4
 Rev. 12-15-80

API #15-119-20-622 0000

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Meade SEC. 27 TWP. 30 RGE. 26 SW
 Location as in quarters or footage from lines:
NE/4, NE/4

Lease Owner Ladd Petroleum Corporation
 Lease Name Post Well No. 2-27
 Office Address P. O. Box 2848, Tulsa, Oklahoma 74101
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
 Date Well Completed 7/21/83
 Application for plugging filed Attached
 Plugging commenced 7/21/83
 Plugging completed 7/21/83
 Reason for abandonment of well or producing formation Dry Hole

Locate Well
 correctly on above
 Section Platt.

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bob Tarbutton
 Producing formation None Depth to top bottom T.D. 5530'
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	1388'	None

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from feet
 to feet for each plug set.

- 50 sx @ 1440'
- 40 sx @ 720'
- 10 sx w/ plug @ 40'
- 15 sx rat hole
- 10 sx mouse hole
- All cement 60/40 pozmix w/ 2% gel & 3% CaCl

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rains & Williamson Oil Company, Inc.

STATE OF Oklahoma COUNTY OF Tulsa, ss.
Kenton D. Miller, Jr. (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) K.D. Miller
P. O. Box 2848, Tulsa, OK 74101
 (Address)

SUBSCRIBED AND SWORN TO before me this 25 day of July, 19 83

My Commission expires: June 11, 1987

Butch Lee Campbell
 Notary Public.
 STATE CORPORATION COMMISSION

JUL 27 1983

Wichita Kansas

15-119-20622-0000

DRILLER'S LOG

COMPANY: Ladd Petroleum Corporation

SEC. 27 T. 30S R. 26W

WELL NAME: Post #2-27

LOC. NE NE

COUNTY: Meade

RIG NO. #5

TOTAL DEPTH 5530'

ELEVATION

COMMENCED: 7-9-83

COMPLETED: 7-21-83

CONTRACTOR: Rains & Williamson Oil Co., Inc.

CASING RECORD:

SURFACE: 8 5/8" @ 1390' w/450 sx. Lite, 1/4# flocele, 2% cc. and 200 sx. Class H, 1/4# flocele, 2% cc.

PRODUCTION: D&A

LOG

(Figures Indicate Bottom of Formations)

Sand & Redbed	417
Sand, Redbed & Clay	1015
Redbed	1354
Shale	2445
Lime & Shale	5530
ROTARY TOTAL DEPTH	5530

RECEIVED
STATE CORPORATION COMMISSION

1983 JUL 24

STATE OF Kansas)

COUNTY OF Sedgwick)


SS:

I, Wilson Rains, President of Rains & Williamson Oil Co., Inc.

upon oath state that the above and foregoing is a true and correct copy of the log of the

Post #2-27 well.

Wilson Rains
Wilson Rains



Subscribed and sworn to before me this 25 day of July, 1983.

My Appointment Expires:
10-4-83

Juanita M. Green
Juanita M. Green