

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Ellsworth County, Sec. 17 Twp. 17 Rge. 10 XXX (W)

Location as "NE/CNW/SW" or footage from lines SW NW NW

Lease Owner Sierra Petroleum Co., Inc.

Lease Name Peterman Well No. #1

Office Address 420 West Douglas, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Was producing oil

Date well completed 9/23/51 19

Application for plugging filed 7/19/56 19

Application for plugging approved 7/20/56 19

Plugging commenced 7/22/56 19

Plugging completed 7/22/56 19

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production July 21 1956

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee

Producing formation Arbuckle Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3316 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	320	None
				5 1/2"	3297	2823'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

PLUGGING REPORT

Plugged back with crushed rock to 3290', dumped 6 sax cement @ 3290' with dump bailer. Top of cement 3250'. Filled hole with mud to 310', set rock bridge, dumped 15 sax cement. Top of cement 260'. Filled with mud to 20', set rock bridge, dumped 5 sax cement for cap.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Miller Casing Pulling Company  
Address Great Bend, Kansas State Plug. License #12

STATE OF Kansas, COUNTY OF Russell, ss.

S. P. Hall (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) S. P. Hall

Russell, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 26th day of July, 1956

My commission expires 10-17-58

Leroy Dietz  
Notary Public.  
STATE CORPORATION COMMISSION

JUL 27 1956

CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC 17 T 17 R 10W  
BOOK PAGE 82 LINE 12

B & R Drilling, Inc.  
Peterman No. 1

SW NW NW Section 17-17-10W  
Ellsowrth County, Kansas

Total Depth: 3297'  
Comm: 9-12-51  
Comp: 9-23-51

Casing	Cement
8 5/8" Set @ 320'	175 sacks of Monarch
5 1/2" Set @ 3297'	75 sacks of Lehigh

Formation	Depth
Shale-Sand-Shells	255
Shale-Shells	475
Redbed	625
Shale-Lime	985
Shale-Shells	1050
Salt-Shale	1295
Shale-Lime	1510
Lime-Shale-Shells	1690
Lime-Shale	2785
Lime	3279
Conglomerate	3294
Arbuckle	3297'

State OF KANSAS)  
                                  )SS  
RUSSELL COUNTY )

I hereby certify that the above information  
is true and correct to the best of my knowledge.

-----*S. P. Hall*-----

Subscribed and sworn to before me this <sup>19th</sup> ~~1st~~ day of <sup>July</sup> ~~October~~, 1956.

-----*Margie Cooper*-----  
Notary Public

My commission expires: <sup>1/30/57</sup> ~~6-15-54~~

**RECEIVED**  
CORPORATION COMMISSION  
JUL 23 1956  
CONSERVATION DIVISION  
Wichita, Kansas

**PLUGGING**  
FILE SEC. 17 T. 17 R. 10W  
BOOK PAGE 82 LINE 12