

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

Reno County, Sec. 17 Twp. 22 Rge. 8 (E) (W)

Location as "NE/CNW/SE" or footage from lines C SE SE

Lease Owner Mull Drilling Company, Inc.

Lease Name Henry Well No. 4

Office Address 1625 Wichita Plaza Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 6-9-67 19

Application for plugging approved 6-10-67 19


Plugging commenced 6-12-67 19

Plugging completed 6-17-67 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation Depth to top Bottom Total Depth of Well 3560 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	228	None
				4 1/2	None	3007

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Moved in. Cleaned out cellar. Sanded to 3500'.

Dumped 5 sacks of cement. Working pipe. Shot pipe at 3000'.

Working Pipe. Pulling Pipe.

Pulling pipe. Plugging well. Set rock bridge at 225'. Dumped 20 sacks of cement. Filled hole and rock bridge. Capped well with 10 sacks of cement.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 22 1967  
6-22-67

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.

Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas COUNTY OF Barton ss.  
J. O. Forbes (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes  
P. O. Box 221 Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 21 day of June, 1967

My commission expires May 27, 1969

(Signature)  
Notary Public.

GABBERT-JONES INC.  
WICHITA, KANSAS  
DRILLERS WELL LOG

15-155-01648-0000

HENRY #4  
 C SE SE SECTION 17-22S-8W  
 RENO COUNTY, KANSAS

COMMENCED: JUNE 26, 1963  
 COMPLETED: JULY 3, 1963

OPERATOR - MULL DRILLING CO., INC.

<u>DEPTH</u>		<u>FORMATION</u>	<u>REMARKS</u>
FROM	TO		
0	40	CLAY	
40	100	SAND	
100	226	RED BED	RAN 8 JOINTS 8-5/8" CASING, SET @ 216' W/ 175 SACKS CEMENT
226	290	RED BED & SHALE	
290	610	CLAY	
610	660	ANHYDRITE & SALT	
660	1180	SHALE & SHELLS	
1180	1710	LIME & SHALE	
1710	1875	LIME	
1875	2705	LIME & SHALE	
2705	2830	LIME	
2830	3135	LIME & SHALE	
3135	3445	LIME	
3445	3520	LIME - SHALE	
3520	3560	CHERTY LIME	
3560	TD		RAN 140 JOINTS 4-1/2" CASING, SET @ 3547' W/ 75 SACKS CEMENT.

RECEIVED  
 JUN 28 1963  
 OREGON DIVISION  
 SEDGWICK, KANSAS

I, E. E. HALL, CERTIFY THIS IS A TRUE AND CORRECT COPY OF THE DRILLER'S LOG FOR THE WELL DRILLED IN C SE SE SECTION 17-22S-8W, RENO COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

*E. E. Hall*

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE ON THIS 8TH DAY OF JULY, 1963, PERSONALLY APPEARED E. E. HALL TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

*Vira A. McKenzie*  
 VIRA A. MCKENZIE, NOTARY PUBLIC

MY COMMISSION EXPIRES OCTOBER 2, 1963