

TIGHT

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Clark SEC. 3 TWP. 30S RGE. 25W E. (W)
 Location as in quarters or footage from lines:
 SW SE NE

Locate Well
 correctly on above
 Section Platt.

Lease Owner Murfin Drilling Company
 Lease Name Fager Well No. 1-3
 Office Address 250 N. Water Wichita, Kansas 67202
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry(c)(L)
 Date Well Completed 7-21-83
 Application for plugging filed 7-21-83
 Plugging commenced 7-21-83
 Plugging completed 7-21-83
 Reason for abandonment of well or producing formation Dry

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Tarbutton
 Producing formation _____ Depth to top _____ bottom _____ T.D. 5450'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Surface				8 5/8"	1041'	none

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

1st plug @ 1440' w/ 50 sx
2nd plug @ 1170' w/ 40 sx
3rd plug @ 510' w/ 40 sx
4th plug @ 40' w/ 10 sx
15 sx in rat hole
Cement used 60/40 Pozmix, 10% gel, 3% CC

AUG 10 1983


CONSERVATION DIVISION
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Murfin Drilling Company

STATE OF Kansas COUNTY OF Sedgwick, ss.

David J. Murfin (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein sworn and the log of the above-described well as
 filed and that the same are true and correct. So help me God.



(Signature) [Signature]
250 N. Water Suite 300
Wichita, (Address) 67202

SUBSCRIBED AND SWORN TO before me this 15th day of August, 1983

Ramona Gunn Notary Public.

My Commission expires: January 25, 1984