

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-097-20,622 0000

LEASE NAME Dirks

WELL NUMBER 1

SPOT LOCATION 1710' FSL
1650' FEL

SEC. 32 TWP. 28 RGE. 18 000 or (W)

COUNTY Kiowa

Date Well Completed 1981

Plugging Commenced 3-12-1986

Plugging Completed 3-13-86

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Gruss Petroleum Management Inc.

ADDRESS 900 Bldg. of SW, 310 W. Texas, Midland, TX 79701

PHONE # (915) 682-8319 OPERATORS LICENSE NO. 9726

Character of Well Oil ADPCC
 (Oil, Gas, D&A, SWD, Input Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Ks. 07

Is ACO-1 filed? yes If not, is well log attached? _____

Producing formation Mississippian Depth to top 3590 bottom 3600' T.D. 4940'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface				8 5/8"	595'	0'
Production				4 1/2"	4924'	2547'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Pumped 2 sks. hulls & 20 sks. cement to 3220' & pressured to 700 lbs.

Pumped 5 sks. gel & 50 sks. cement 1200' to 1050'

Pumped 40 sks. cement 625' to 500'

Put bridge & 10 sks. cement 40' to 0'

Cut off 8 5/8", 3' below ground level

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Midwest Casing Pulling Service License No. 6497

Address Box F, Sublette, Ks, 67877

STATE OF Kansas COUNTY OF Haskell, ss.

I, Edgar J. Eves

(~~Employer or Operator~~) or
 (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Edgar J. Eves

(Address) Box F, Sublette, Ks. 67877

SUBSCRIBED AND SWORN TO before me this 24th day of March, 1986

My Commission expires: 12-6-88

Sondra L. Eves
 Notary Public



APR - 7 1986

CONSERVATION DIVISION
 Wichita, Kansas