

15-025-20695-0000

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Clark SEC. 3 TWP. 30S RGE. 25 XR/W  
 Location as in quarters or footage from lines:

2310' FWL & 2260' FWL

	⊙		

Lease Owner Santa Fe Energy Company

Lease Name Lena D. Boucher Well No. 1-3A

Office Address Williams Center Tower One, Suite 500  
one West 3rd, Tulsa, OKla 74103

Character of Well (Completed as Oil, Gas or Dry Hole): Dry hole

Date Well Completed May 19, 1983

Application for plugging filed May 20, 1983 (over phone)

Plugging commenced May 22, 1983

Plugging completed May 22, 1983

Reason for abandonment of well or producing formation Dry hole.

Locate Well  
 correctly on above  
 Section Platt.

Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Paul Luthi

Producing formation none Depth to top N/A bottom N/A T.D. 5365'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	1407'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

At the time of plugging the hole, the hole was full of 9.0 ppg 45 viscosity drilling fluid (mud). This mud was left in the hole below and between all cement plugs. The well was plugged as follows by spotting cement plugs through drill pipe. All plugs consisted of 60/40 Class "H" Pozmix cement containing 2% total gel and 3% Calcium Chloride.

Plug #1 from 1395' to 1220' with 50 sacks cement.

Plug #2 from 865' to 743' with 35 sacks cement.

Plug #3 from 310' to 205' with 30 sacks cement.

Plug #4 from 40' to 5' with 25 sacks cement (placed wooden plug @ 40' also)

Filled rathole with 15 sacks of cement and mousehole with 10 sacks of cement.

The 8 5/8" surface casing was cut off three (3) feet below ground level and steel plate welded on top. (If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Services

Box 1598 Liberal, Kansas 67901

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Sammy N. Morgan, Sr. Drilling Engr. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Sammy N. Morgan  
 (Address)

SUBSCRIBED AND SWORN TO before me this \_\_\_\_\_ day of \_\_\_\_\_, 19 \_\_\_\_\_

Sam J. Tidwell  
 Notary Public.

My Commission expires: 7-12-87