

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-033-20,671 0000

LEASE NAME Ralph Baker

WELL NUMBER 5

1320' Ft. from S Section Line

3960' Ft. from E Section Line

SEC. 36 TWP. 33 RGE. 20 (N or W)

COUNTY Comanche

Date Well Completed 3-17-1985

Plugging Commenced 6-24-1991

Plugging Completed 6-27-1991

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR R.J. Patrick Operating Co.

ADDRESS Box 1314 - Liberal, Ks. 67901

PHONE# (316) 624-8483 OPERATORS LICENSE NO. 6528

Character of Well Oil & Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6-21-1991 (date)

by Richard Lacy (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Swope Depth to Top 4758' Bottom 4813' T.D. 4850'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED
STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put in	Pulled out
Surface				8 5/8"	678'	0'
Production				4 1/2"	4835'	3100'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pump 4 Sks. hulls and 40 Sks. cement to 4500' - pressured to 750 lbs.

Pump 40 Sks Cement 950' to 830' Mud 830' to 700'

Pump 50 Sks. cement 700' to 550' - Mud to 40'

Put Bridge and 10 Sks. cement 40' to 3', cut off 8 5/8" & cap

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor MIDWEST CASING PULLING SERVICE License No. 6497

Address Box F, Sublette, Ks. 67877

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: R. J. Patrick Operating

STATE OF Kansas COUNTY OF Haskell, ss.

I, Edgar J. Eves (Employee of Operator) or ~~Notary Public~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Edgar J. Eves

(Address) Box F, Sublette, Ks. 67877



SUBSCRIBED AND SWORN TO before me this 2nd day of July, 1991

Sandra L. Eves
Notary Public

My Commission Expires: 12-6-92

DRILLER'S LOG

R.J. Patrick Operating
P O Box 1314
Liberal, Ks. 67901

Ralph Baker # 5
Comanche County

Commenced: 2-19-84
Completed: 2-28-84

delete

Surface Casing: Run 16 jts. new 24# 8 5/8 cgs.
675.7', Run shoe; one Centrolizer; insert float
at 647' and basket at 120', Cement w/200 sx Lite
~~w/200 sx Lite~~ w/2% CC, w/150 class H w/3%
cc., good circ. thru out job circ. 40 bbls
cement to pit. Plug down at 1:55 P.M. Landed
cgs. at 688 K.B. w/loading jt.

Total Depth: 4850'

FORMATION	FROM	TO	REMARKS
Sand and Clay	0'	560'	LTD 4846'
Bed	560'	688'	
Bed, Clay, Lime	688'	1330'	
me & Shale	1330'	2155'	
me & Shale	2155'	3375'	
me, Shale, & chalk	3375'	3582'	
me & Shale	3582'	3735'	
me	3735'	3880'	
me & Shale	3880'	4726'	
me	4726'	4850'	


RECEIVED
STATE CORPORATION COMMISSION
JUN 14 1991
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the log on the above captioned well to the best of my knowledge.

NRG Drilling, Inc.

By Elmer Jack Taylor
Elmer Jack Taylor Vice President

Subscribed and sworn to before me this 28 day of February 19 85



Lexanna L. Allen
Lexanna L. Allen

My commission expires April 6, 1988

RECEIVED MAR - 7 1985