


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Comanche County, Sec. 6 Twp. 31 Rge. (E) 17 (W)

Location as "NE/CNW/SW" or footage from lines C SW SE

Lease Owner Aylward Drilling Company

Lease Name Yost Well No. 1

Office Address 909 First National Bank Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed December 23, 19 63

Application for plugging filed December 22, 19 63

Application for plugging approved December 22, 19 63

Plugging commenced December 23, 19 63

Plugging completed December 23, 19 63

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie Elving

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5472 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	293	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 280'
Set plug with 25 sacks cement and 1 sack bulls at 280'
Filled with heavy mud to 40'
Set plug with 10 sacks cement and 1 sack bulls at 40'
Bridged rathole and filled with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

JAN 23 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Company tools

Address _____

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Charles D. Williams (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles D. Williams

909 1st Nat'l Bank Bldg, Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 27th day of December, 19 63

My commission expires December 11, 1965

Duane Jessup
DUANE JESSUP
Notary Public.



15-033-00093-0000

YOST #1

Casing Record:
8 5/8" - 293'

Company: Aylward Drilling Company
Contractor: Aylward Drilling Company

Location: C SW SE 6-31-17W
Comanche County
Kansas

Commenced: November 26, 1963
Completed: December 23, 1963

Elev. 2111 DF - 2114 RB

	<u>From</u>	<u>To</u>	<u>Remarks</u>
Surface Clay	0	20	Set 8 5/8" surface pipe @ 293' w/325 sacks.
Gyp Rock	20	45	
Sandy Red Bed	45	90	
Red Rock & Shales	90	185	Geological Tops: (Log)
Sand	185	255	
Red Bed & Shale	255	1400	Topeka 3720
Shale & Shells	1400	2138	Heebner 4216
Sandy Lime & Shale	2138	2325	Douglas 4249
Lime & Shale	2325	2505	Brown Lime 4380
Lime with shale	2505	2700	Lansing-Kansas City 4400
Lime & Shale	2700	3605	Base/Kansas City 4764
Lime	3605	3650	Marmaton 4777
Lime & Shale	3650	3800	Mississippian 5021
Lime	3800	3935	Viola 5368
Lime & Shale	3935	4140	R.T.D. 5471
Lime	4140	4187	
Lime & Shale	4187	4500	DST 3185-3212 Open 70"
Lime	4500	4577	Rec. 135' mud
Lime & Shale	4577	4615	IBHP 1153# / 30" - FBHP 1105# / 30"
Lime & Chert	4615	4675	FP 78#-90#
Lime	4675	4865	
Lime & Shale	4865	4909	DST 5015-50 Open 70"
Lime & Shale Breaks	4909	4925	Rec. 30' mud
Lime & Shale	4925	4974	IBHP 73# - FBHP 52# / 30"
Lime & Shert	4974	4981	FP 41#-43#
Lime	4981	5005	
Lime & Shale	5005	5090	DST 5050-90 Open 70"
Chert & Lime	5090	5103	Rec. 40' mud
Lime	5103	5329	IBHP 220# - FBHP 247# / 30"
Lime & Chert	5329	5332	FP 24#-34#
Lime	5332	5370	
Lime & Chert	5370	5472 T.D.	D & A

RECEIVED
STATE CORPORATION COMMISSION

JAN 23 1964

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

Charles D. Williams

Subscribed and sworn to before me this 27th day of December, 1963

Duane Jessup
DUANE JESSUP Notary Public

My commission expires December 11, 1965