

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-025-20616-00-00
LEASE NAME MINNEOLA UNIT(Harris 1-3)

TYPE OR PRINT WELL NUMBER 6-1

NOTICE: Fill out completely 990 Ft. from S Section Line
and return to Cons. Div. 4950 Ft. from E Section Line
office within 30 days

LEASE OPERATOR Murfin Drilling Co., Inc. SEC 3 TWP. 30S RGE25W (E) or (W)
ADDRESS 250 N. Water, Suite 300; Wichita, KS 67202 COUNTY CLARK
PHONE # () 267-3241 OPERATORS LICENSE NO. 30606 Date Well Completed _____
Character of Well OIL (Oil, Gas, D&A, SWD, Input, Water Supply Well) Plugging commenced 7/10/02
Plugging Completed 7/10/02

The plugging proposal was approved on 7/02 (date)
by STEVE MIDDLETON w/KCC DODGE CITY, KS. (KCC District
Agent's Name).

Is ACO-1 filed? no If not, is well log attached? no
Producing Formation MORROW Depth to Top 5320 Bottom 5332 TD 5500' Show
depth and thickness of all water oil and gas formations.

OIL, GAS, OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		surface	1404	8 5/8	1404	0
		production	5496	5 1/2	5496	2700'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Plugged well as follows: Bridge plug set @ 5270. Plugged surface w/300# hulls, 10sxs gel, 50 sxs cmt. 10 sxs get, 100# hulls, released plug and 150 sxs cmt 60/40 pos, 6% gel. Well P/A. Witnessed and approved by STEVE MIDDLETON w/ KCC DODGE CITY, KS.

Name of Plugging Contractor Murfin Drilling Company, Inc. License No. 30606 Address
250 N. Water, Suite 300; Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company, Inc.


STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Tom W. Nichols, Production Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]
(Address) Wichita, KS

SUBSCRIBED AND SWORN TO before me this 6 th day of August, 2002

Notary Public - Barbara J. Dodson [Signature]
My Commission Expires: 12/16/03 Form CP-4

Revised 05-88



RECEIVED
AUG 08 2002
KCC WICHITA

OK

Mike's Testing & Salvage Inc.

P.O. Box 467
Chase, KS 67524

COPY
Invoice

Date	Invoice #
7/31/2002	9380

Bill To
Murfin Drilling Co., Inc. 250 N. Waster, Suite 300 Wichita, Kansas 67202

RECEIVED

AUG 01 2002

36 P4A RK

P.O. No.	Lease	County
	Minneola 6-1	Clark

Qty	Description	Rate	Amount
14	Hours Rig Time	120.00	1,680.00T
1	Shot	150.00	150.00T
2	Sacks Cement	10.50	21.00T
2	Hours - Truck Move Floor	50.00	100.00T
1	5-1/2" Collar	45.00	45.00T
4.5	Hours - Welder	40.00	180.00T
	Solvent	6.00	6.00T
1	Night Out of Town Expense	135.00	135.00
	6-27-02 Log Tech set CIBP @5270'.		
	6-29-02 Welder took head apart and welded 5-1/2" collar.		
	7-9-02 Moved in on location, rigged up, set in floor, went and got cement, dumped 2 sacks cement on top of CIBP. 6 Hours.		
	7-10-02 Drove to location, shot and worked pipe loose @2700', tore down and moved off. 8 Hours. <i>LAYed down CASIP9</i>		
	7-16-02 Welder cut head off and welded 8-5/8" collar.		
	7-17-02 Allied Cementing plugged surface with 300# hulls, 10 sacks gel, 50 sacks cement, 10 sacks gel, 100# hulls, released plug and 150 sacks cement. 60/40 pos, 6% gel. Plugging complete.		
	Sales Tax	6.30%	137.47
		Total	\$2,454.47

RECEIVED
AUG 08 2002
KCC WICHITA