

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202 TYPE OR PRINT

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-025-20594-00-00
LEASE NAME MINNEOLA UNIT(Patton1-3
Swift)

WELL NUMBER 1-1
NOTICE: Fill out **completely** 660 Ft. from S Section Line
and return to Cons. Div. 660 Ft. from E Section Line
office within 30 days

LEASE OPERATOR Murfin Drilling Co., Inc. SEC 3 TWP. 30S RGE25W (E) or (W)
ADDRESS 250 N. Water, Suite 300; Wichita, KS 67202 COUNTY CLARK
PHONE # () 267-3241 OPERATORS LICENSE NO. 30606 Date Well Completed 6/19/82
Character of Well OIL (Oil, Gas, D&A, SWD, Input, Water Supply Well) Plugging commenced 7/16/02
Plugging Completed 7/17/02

The plugging proposal was approved on 7/17/02 (date)
by STEVE MIDDLETON w/KCC DODGE CITY, KS. (KCC District
Agent's Name).

Is ACO-1 filed? no If not, is well log attached? no
Producing Formation MORROW Depth to Top 5318 Bottom 5380 OA TD 5500' PBTD5450'

Show depth and thickness of all water oil and gas formations.

OIL, GAS, OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		surface	1410	8 5/8	845	0
		production	5494	5 1/2	5494	2720'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Plugged well as follows: Allied set cement plugs. Shot csg. @ 2720'. Plugged surface w/10 sxs gel, 50 sxs cmt., 10 sxs gel, released plug and 150 sxs cmt. 60/40 pos. 6% gel. Well P/A. Witnessed and approved by STEVE MIDDLETON w/ KCC DODGE CITY, KS.

Name of Plugging Contractor Murfin Drilling Company, Inc. License No. 30606 Address
250 N. Water, Suite 300; Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company, Inc.


STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Tom W. Nichols, Production Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]
(Address) Wichita, KS

SUBSCRIBED AND SWORN TO before me this 6 th day of August, 2002

Notary Public - Barbara J. Dodson [Signature]
My Commission Expires: 12/16/03 Form CP-4 Revised 05-88



RECEIVED
AUG 08 2002
KCC WICHITA

OR

Mike's Testing & Salvage Inc.

P.O. Box 467
Chase, KS 67524

Invoice

Date	Invoice #
7/31/2002	9382

COPY

RECEIVED

AUG 01 2002

36 FA RK

Bill To
Murfin Drilling Co., Inc. 250 N. Waster, Suite 300 Wichita, Kansas 67202

P.O. No.	Lease	County
	Minneola 1-1	Clark

Qty	Description	Rate	Amount
18	Hours Rig Time	120.00	2,160.00T
1	Shot	150.00	150.00T
5	Sacks Cement	10.50	52.50T
	Sand	20.00	20.00T
	Solvent	6.00	6.00T
1	Night Out of Town Expense	135.00	135.00
1	5-1/2" Collar	45.00	45.00T
4.5	Hours - Welder	40.00	180.00T
	6-27-02 Log Tech set CIBP @5320'.		
	6-28-02 Welder took head apart and welded 5-1/2" collar.		
	7-16-02 Moved to location, set in rig and rigged up, ran sand to 5250', dumped 5 sacks cement on top, set in floor and rigged up. Welder cut head off and welded 8-5/8" collar.		
	7-17-02 Drove to location, shot and worked pipe loose @2720', Allied Cementing plugged surface with 10 sacks gel, 50 sacks cement, 10 sacks gel, released plug and 150 sacks cement. 60/40 pos, 6% gel. Plugging Complete. 9 Hours.		
	Sales Tax	6.30%	164.65
Total			\$2,913.15

RECEIVED
AUG 08
KCC WICHITA