

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-025-20708-0000
LEASE NAME MINNEOLA UNIT(Harris 2-3)

TYPE OR PRINT WELL NUMBER 5-2

NOTICE: Fill out completely 330 Ft. from S Section Line
and return to Cons. Div. 2970 Ft. from E Section Line
office within 30 days

LEASE OPERATOR Murfin Drilling Co., Inc. SEC 3 TWP. 30S RGE25W (E) or (W)
ADDRESS 250 N. Water, Suite 300; Wichita, KS 67202 COUNTY CLARK
PHONE # () 267-3241 OPERATORS LICENSE NO. 30606 Date Well Completed 7/06/83
Character of Well OIL (Oil, Gas, D&A, SWD, Input, Water Supply Well) Plugging commenced 7/10/02
Plugging Completed 7/17/02

The plugging proposal was approved on 7/17/02 (date)
by STEVE MIDDLETON w/KCC DODGE CITY, KS. (KCC District
Agent's Name).

Is ACO-1 filed? no If not, is well log attached? yes

Producing Formation MORROW Depth to Top 5290 Bottom 5294 TD 5468'

Show depth and thickness of all water oil and gas formations.

OIL, GAS, OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		surface	677	8 5/8	677	0
		production	5466	5 1/2	5466	2500'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Plugged well as follows: Bridge plug set @ 5100. Shot csg. @ 2520' csg released, pulled & laid down. Plugged surface w/300# hulls, 10 sxs gel, 50 sxs cmt., 10 sxs gel 100# hulls, released plug and 150 sxs cmt. 60/40 pos, 6% gel. Well P/A. Witnessed and approved by STEVE MIDDLETON w/ KCC DODGE CITY, KS.

Name of Plugging Contractor Murfin Drilling Company, Inc. License No. 30606 Address
250 N. Water, Suite 300; Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Tom W. Nichols, Production Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]
(Address) Wichita, KS

SUBSCRIBED AND SWORN TO before me this 6 th day of August, 2002

RECEIVED

Notary Public - Barbara J. Dodson

Barbara J. Dodson

My Commission Expires: 12/16/03 Form CP-4 Revised 05-88

AUG 08 2002

KCC WICHITA



OP

Mike's Testing & Salvage Inc.

P.O. Box 467
Chase, KS 67524

Invoice

Date	Invoice #
7/31/2002	9381

Bill To
Murfin Drilling Co., Inc. 250 N. Waster, Suite 300 Wichita, Kansas 67202

COPY

RECEIVED

AUG 01 2002

36-PAH-RK

P.O. No.	Lease	County
	Minneola 5-2	Clark

Qty	Description	Rate	Amount
15	Hours Rig Time	120.00	1,800.00T
2	Shots	150.00	300.00T
2	Sacks Cement	10.50	21.00T
2	Hours - Welder	40.00	80.00T
	Solvent	6.00	6.00T
1	Night Out of Town Expense	135.00	135.00
	6-27-02 Log Tech set CIBP @5100'		
	7-10-02 Drove to location, set in rig and rigged up, tried to cut out plate but couldn't. 2 Hours.		
	7-11-02 Drove to location, dumped 2 sacks cement on top of CIBP. Set in floor and rigged up, got plate cut out, shot pipe @2700 and 2500', worked pipe loose, layed down 20 jts. 10 Hours.		
	7-12-02 Drove to location, finished laying down 5-1/2" casing. Tore down and moved off. 3 Hours.		
	7-16-02 Welder cut head off and welded 8-5/8" collar.		
	7-17-02 Allied Cementing plugged surface with 300# hulls, 10 sacks gel, 50 sacks cement, 10 sacks gel, 100# hulls. released plug and 150 sacks cement. 60/40 pos, 6% gel Plugging Complete		
	Sales Tax	6.30%	139.04
Total			\$2,481.04

RECEIVED
AUG 08 2002
KCC WICHITA