

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 30930
Name: PAR, Inc.
Address 1: 2201 East Wilshire Blvd.
Address 2: _____
City: Oklahoma City State: OK Zip: 73111 + _____
Contact Person: Pat Rigual
Phone: (405) 478 - 0385
Type of Well: (Check one) ☐ Oil Well ☐ Gas Well ☐ OG ☐ D&A ☐ Cathodic
☐ Water Supply Well ☐ Other: _____ ☐ SWD Permit #: _____
☒ ENHR Permit #: E-23,294 ☐ Gas Storage Permit #: _____
Is ACO-1 filed? ☒ Yes ☐ No If not, is well log attached? ☐ Yes ☐ No
Producing Formation(s): List All (If needed attach another sheet)
Cattleman SS Depth to Top: 1845 Bottom: 1853 T.D. 1900
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 019-24,331-00-01

Spot Description: _____
SE SW NE NE Sec. 17 Twp. 34 S. R. 10 ☒ East ☐ West
4,095 Feet from ☐ North / ☒ South Line of Section
790 Feet from ☒ East / ☐ West Line of Section

Footages Calculated from Nearest Outside Section Corner:

☐ NE ☐ NW ☒ SE ☐ SW

County: Chautauqua

Lease Name: Kelly Well #: 11

Date Well Completed: _____

The plugging proposal was approved on: 11/31/2012 (Date)

by: Steve Korf (KCC District Agent's Name)

Plugging Commenced: 12/3/2012

Plugging Completed: 12/3/2012

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Cattleman SS	Oil	Surface	7"	40'	None
		Production	4.5"	1,900'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran 1" to 1850'. Gel hole. Spot 50' of cement at 1850'. Pull 1" to 750'. Spot 50' of cement at 750'. Pull 1" to 550' and cement to surface with 55 sacks. Total sacks used was 65

RECEIVED
DEC 26 2012
KCC WICHITA

Plugging Contractor License #: 32884 Name: Elmore's Inc
Address 1: 776 Highway 99 Address 2: _____
City: Sedan State: Kansas Zip: 67361 + _____
Phone: (620) 725 - 5538

Name of Party Responsible for Plugging Fees: Pat Rigual / PAR, Inc.

State of Kansas County, Chautauqua, ss.

Thomas H. Oast

(Print Name)

☒ Employee of Operator or ☐ Operator on above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: _____

STATEMENT

10333

ELMORE'S INC.

Box 87 - 776 HWY99

Sedan, KS 67361

Cell: (620) 249-2519

Eve: (620) 725-5538

Date

12-3-12

RECEIVED

DEC 26 2012

KCC WICHITA

Customer Pan
Address _____
City _____ State _____ Zip _____

Qty.	Description	Price	Amount
4	Pulling Unit	120.00	480.00
3	Cement Pump	110.00	330.00
3	Water Truck	85.00	255.00
1	Baukk Tank	85.00	85.00
1850'	1" Tubin	.10	185.00
65 SK	Cement	10.00	650.00
2 SK	Gel	16.00	32.00
			2012.00
	Plug Job Kelly	Tax	167.41
		\$	2184.41
	Ran 1" Tubin To 1850'		
	Gel Note Spotted 50'		
	Cement Plug on Bottom Pulled		
	1" Up to 750' Spotted 50'		
	Cemen Plug Pulled Up to 550'		
	Cemented To Surface With		
	55 SKS Cementa		

Thank You - We appreciate your business!

Rec'd. by _____

TERMS: Account due upon receipt of services. A 1 1/2% Service Charge, which is an annual percentage rate of 18% will be charged to accounts after 30 days.