

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-025-20685 0000  
LEASE NAME MINNEOLA UNIT (Patton 2-3)  
WELL NUMBER 3-2

NOTICE: Fill out **completely** and return to Cons. Div. office within 30 days  
1980 Ft. from S Section Line  
1980 Ft. from E Section Line

LEASE OPERATOR Murfin Drilling Co., Inc. SEC 3 TWP. 30S RGE25W (E) or (W)  
ADDRESS 250 N. Water, Suite 300; Wichita, KS 67202 COUNTY CLARK  
PHONE # ( ) 267-3241 OPERATORS LICENSE NO. 30606 Date Well Completed 4/30/83  
Character of Well OIL (Oil, Gas, D&A, SWD, Input, Water Supply Well) Plugging commenced 7/12/02  
Plugging Completed 7/17/02

The plugging proposal was approved on 7/17/02 (date)  
by w/KCC DODGE CITY, KS. (KCC District Agent's Name).

Is ACO-1 filed? no If not, is well log attached? no  
Producing Formation MORROW Depth to Top 5294 Bottom 5304 TD 5460' Show  
depth and thickness of all water oil and gas formations.

OIL, GAS, OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		surface	1082	8 5/8	1082	0
		production	5456	5 1/2	5456	2730

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

Plugged well as follows: Shot csg. @ 2730' .Plugged surface w/300# hulls, 10 sxs gel, 50 sxs cmt, 10 sxs gel, 100#hulls, released plug and 150 sxs cmt. 60/40 pos 6% gel. Well P/A. Witnessed and approved by STEVE MIDDLETON w/ KCC DODGE CITY, KS.

Name of Plugging Contractor Murfin Drilling Company, Inc. License No. 30606 Address  
250 N. Water, Suite 300; Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company, Inc.


STATE OF KANSAS COUNTY OF SEDGWICK .SS.

Tom W. Nichols, Production Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]  
(Address) Wichita, KS

SUBSCRIBED AND SWORN TO before me this 6 th day of August, 2002

Notary Public - Barbara J. Dodson [Signature]  
My Commission Expires: 12/16/03 Form CP-4 Revised 05-88



RECEIVED  
AUG 08 2002  
KCC WICHITA

OR

Mike's Testing & Salvage Inc.

P.O. Box 467  
Chase, KS 67524

# Invoice

Date	Invoice #
7/31/2002	9383

<b>Bill To</b>
Murfin Drilling Co., Inc. 250 N. Waster, Suite 300 Wichita, Kansas 67202

**COPY**

RECEIVED

AUG 01 2002

36 RAR RK

P.O. No.	Lease	County
	Minneola 3-2	Clark

Qty	Description	Rate	Amount
14	Hours Rig Time	120.00	1,680.00T
1	Shot	150.00	150.00T
2	Sacks Cement	10.50	21.00T
2	Hours - Welder	40.00	80.00T
	Thread Dope	25.00	25.00T
	Solvent	6.00	6.00T
1	Night Out of Town Expense	135.00	135.00
	6-27-02 Log Tech set CIBP @5277'.		
	7-12-02 Moved to location, set in rig, rigged up, dumped 2 sacks of cement on top of CIBP. Set in floor and rigged up. 6 Hours.		
	7-15-02 Drove to Clark County and topped off Minneola 13-1, 12-2, 10-1 & 9-1 with ready-mix. 3 Hours.		
	7-16-02 Drove to location, shot and worked pipe loose @2730', layed down 5-1/2" casing, tore down and moved off. Welder cut off head and welded 8-5/8" collar. 5 Hours.		
	7-17-02 Allied Cementing plugged surface with 300# hulls, 10 sacks gel, 50 sacks cement, 10 sacks gel, 100# hulls, released plug, and 150 sacks cement. 60/40 pos, 6% gel. Plugging Complete.		
	Sales Tax	6.30%	123.61
<b>Total</b>			<b>\$2,220.61</b>

RECEIVED  
AUG 08 2002  
KCC WICHITA