

15-057-00111-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

FORD County. Sec. 34 Twp. 25 Rge. 21 (E) W (W)
Location as "NE/CNWSW" or footage from lines. C NE NW
Lease Owner MORRISON PRODUCING COMPANY
Lease Name HAMMEKE Well No. 1
Office Address P. O. BOX 712, EL DORADO, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed MAY 30, 1964 19
Application for plugging filed MAY 30, 1964 19
Application for plugging approved MAY 30, 1964 19
Plugging commenced MAY 30, 1964 19
Plugging completed MAY 30, 1964 19
Reason for abandonment of well or producing formation DRY HOLE

NORTH

	X		

Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well HUGH SCOTT, SUBLETTE, KANSAS
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4844 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	352	7"	352'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGED WITH 10 SX CEMENT @ 700 FT.;
10 SX CEMENT @ 350 FT.; 5 SX CEMENT
PLUS 1/2 SX HULLS @ 35 FT. TO SURFACE.

RECEIVED
STATE CORPORATION COMMISSION

JUN 18 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor CHEMICAL & TECHNICAL SERVICES, INC.
Address P. O. BOX D, HILL CITY, KANSAS

STATE OF KANSAS, COUNTY OF GRAHAM, ss.
DANIEL F. MCCARTHY (employee ~~of~~ ~~operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Daniel F. McCarthy
P. O. BOX D, HILL CITY, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of June, 1964

My commission expires January 20, 1968
My commission expires _____

Lena Zeller
Notary Public.



CONTRACTOR'S WELL LOG

OWNER:
 CONTRACTOR:
 WELL:
 LOCATION:
 COMMENCED:
 COMPLETED:

MORRISON PRODUCING COMPANY
 CHEMICAL & TECHNICAL SERVICES, INC.
 HAMMEKE # 1
 C NE NW SEC. 34-25S-21W
 FORD COUNTY, KANSAS
 MAY 14, 1964
 MAY 30, 1964

0	105	SURFACE CLAY & SAND
105	235	SANDY SHALE
235	305	SAND
305	352	SHALE
352	1300	SHALE & SAND
1300	1379	SHALE & RED BED
1379	1431	ANHYDRITE
1431	1720	RED BED, SHALE & LIME
1720	2105	SHALE
2105	2649	LIME & SHALE
2649	2893	LIME
2893	3863	LIME & SHALE
3863	3960	LIME
3960	4135	LIME & SHALE
4135	4727	LIME
4727	4775	SAND & SHALE
4775	4814	LIME
4814	4844	LIME & CHERT
4844		ROTARY TOTAL DEPTH

RECEIVED
 STATE CORPORATION COMMISSION

JUN 18 1964

CONSERVATION DIVISION
 Wichita, Kansas

SET 7" SURFACE PIPE AT 352 FT. WITH 165 SX CEMENT

DRY & ABANDONED

WE HEREBY CERTIFY THAT THE ABOVE IS A CORRECT AND ACCURATE LOG OF THE ABOVE MENTIONED WELL, AS SHOWN ON THE DAILY DRILLING REPORTS.

CHEMICAL & TECHNICAL SERVICES, INC.

BY: *D. J. McCarthy*
 ASST. TREASURER

SUBSCRIBED AND SWORN TO BEFORE ME THIS 17th DAY OF JUNE, 1964.

My Commission Expires January 20, 1968

Don Lester
 NOTARY PUBLIC