

API NUMBER 15-101-21,467-0000

LEASE NAME Cartmill #1

WELL NUMBER 1

1650 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 22 TWP. 17 RGE. 28W (E) or (W)

COUNTY Lane

Date Well Completed 4-26-88

Plugging Commenced 4-26-88

Plugging Completed 4-26-88

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Perry Petroleum, Inc.

ADDRESS P.O. Box 580, Hutchinson, KS 67504-0580

PHONE# (316) 662-4401 OPERATORS LICENSE NO. 06761

Character of Well Dry

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on April 21, 1988 (date)

by Steve Durant (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. 1st plug @ 2130' w/50 sacks 60/40poz. thru D.P.--2nd plug @ 1320' w/80 sacks 60/40poz. thru D.P.--3rd plug @ 240' w/40 sacks 60/40poz. thru D.P.--Top Plug @ 40' w/10 sacks 60/40poz. 15 sacks in rat hole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Lobo Drilling Company License No. 5864

Address P.O. Box 877

STATE OF Kansas COUNTY OF Barton, ss.


(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ernie Hughes

(Address) P.O. Box 877, Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 29 day of April, 19 88

Dorothy M. Hague
 Notary Public



RECEIVED
 MAY 6 1988
 Form CP-4
 Revised 07-87

DRILLERS WELL LOG

15-101-21467-0000

DATE COMMENCED: April 18, 1988
DATE COMPLETED: April 26, 1988

Perry Petroleum Company
Cartmill #1
SE NW SW
Sec.22-T17-R28W
Lane County, KS

ELEVATION: 2754' K.B.

0- 160' Clay, Sand
160- 219' Blue Shall
219-1419' Shales, Sand
1419-1680' Shales, Limes
1680-1881' sand
1881-2128' Shales
2128-2161' Anhydrite
2161-2760' Shale, Sand
2760-3024' Lime, Shale
3024-3222' Shale, Lime
3222-4040' Lime, Shales
4040-4195' Lime
4195-4361' Lime, Shales
4361-4600' Lime
4600 RTD

Surface Pipe: Set
217' of 8 7/8", 24#
with 140 sacks 60/40 pozmix
2% gel, 3% c.c.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss

ERVIN NEIGHBORS of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Ervin Neighbors
Ervin Neighbors

SUBSCRIBED AND SWORN to before me this 29 day of April, 1988.

Dorothy M. Hague
Notary Public



RECEIVED
STATE CONSERVATION COMMISSION

MAY 0 4 1988

CONSERVATION DIVISION
Wichita, Kansas

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date... 4 - 18 - 88 month day year

API Number 15-101-21467-0000

OPERATOR: License # 06761 Name Perry Petroleum, Inc. Address P.O. Box 580 City/State/Zip Hutchinson, KS. 67504-0580 Contact Person Jim Perry Phone (316) 662-4401

SE NW SW Sec. 22. Twp. 17. S, Rg. 28. West 1650 Ft. from South Line of Section 4290 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 584 Name Loba Drilling Company City/State Great Bend, KS

Nearest lease or unit boundary line 990 West feet County Lane

Well Drilled For: Well Class: Type Equipment: X Oil Storage Infield X Mud Rotary X Gas Inj Pool Ext Air Rotary OWWO Expl Wildcat Cable

Lease Name Cartmill Well # 1 Ground surface elevation 2749 feet MSL Domestic well within 330 feet: yes X no Municipal well within one mile: yes X no

If OWWO: old well info as follows:

Depth to bottom of fresh water 200' Depth to bottom of usable water 1300'

Operator Well Name Comp Date Old Total Depth

Surface pipe by Alternate: Surface pipe planned to be set 200' 200' 1-2X

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Conductor pipe required Projected Total Depth 4600' feet Formation Mississippi

Date 1-15-88 Signature of Operator or Agent James S. Perry Title PRESIDENT

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required 200 feet per Alt. X 2

This Authorization Expires 10-18-88 Approved By RCM 4-8-88

EXPIRE DATE: 4-23-88

SPUD 4-18-88 200' - 8 3/8" Richard

SW Sec. 22. Twp. 17. S, Rg. 28. West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ ft. deep. base of anhydrite formation with 50. SX feet of cement
2nd plug @ ft. deep. base of cheyenne or formation with 80. SX feet of cement
3rd plug @ ft. deep. 30' below base of surface pipe 40. SX feet of cement
4th plug @ ft. deep. 800' or formation with 40. SX feet of cement
5th plug @ ft. deep. 40' or formation with 10. SX feet of cement

(2) Rathole to surface minus 5 feet 15 sx of cement (b) Mousehole to surface minus 5 feet 10 sx of cement

PUSHER Garvin Doughlas TD 4600' FORMATION MISS SURFACE PIPE 8 3/8 @ 217 ANHYDRITE 2128 ELEVATION 2749 STARTING TIME & DATE 4:30 AM COMPLETION TIME & DATE 7:30 AM 1st PLUG @ 2130 FT. W/ 50 SX 2nd PLUG @ 1320 FT. W/ 80 SX 3rd PLUG @ 240 FT. W/ 40 SX 4th PLUG @ 40-0 FT. W/ 10 SX RAT HOLE CIRCULATED W/ 15 SX MOUSE HOLE CIRCULATED W/ NA SX WATER WELL PLUGGED w/ Irrigation well SX CEMENT COMPANY 614 Pot 610 Allied TECHNICIAN SD. D.G