


STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 Give All Information Completely  
 Make Required Affidavit  
 Mail or Deliver Report to:  
 Conservation Division  
 State Corporation Commission  
 800 Bitting Building  
 Wichita, Kansas

OR  
**FORMATION PLUGGING RECORD** Strike out upper line when reporting plugging off formations.

Ellis County. Sec. 17 Twp. 15 Rge. (E) 12 (W)  
 Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. NW-NW-SW  
 Lease Owner. Sunray Oil Corporation  
 Lease Name. Hauschild Well No. 1  
 Office Address. Box 195, Great Bend, Kansas  
 Character of Well (completed as Oil, Gas or Dry Hole) dry hole  
 Date well completed. 9/30/ 1944  
 Application for plugging filed. 19  
 Application for plugging approved. 10/6/ 1944  
 Plugging commenced. 10/1/ 1944  
 Plugging completed. 10/1/ 1944  
 Reason for abandonment of well or producing formation dry hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production. 19  
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well. Kerr  
 Producing formation. Reagan (dry) Depth to top. 3608 Bottom. 3621 Total Depth of Well. 3621 Feet  
 Show depth and thickness of all water, oil and gas formations.

Formation	Content	From	To	Size	Put In	Pulled Out
Dakota	water	580	889	15 $\frac{1}{2}$	80'	none
Anhydrite	dry	1208	1230	8 5/8	1219'	"
Topeka	"	2792				
Lsg.	"	3279				
Congl.	"	3592				
Reagan	"	3608	3621			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole filled with heavy mud from 3621 to 1250; hole bridged w/ wood plug & 20 sx cement from 1250 to 1185; hole filled w/ heavy mud from 1185 to 50' set wood plug, then filled w/ cement to bottom of cellar & mudded to surface.

**PLUGGING**  
 FILE 17 15 1944  
 BOOK PAGE 134 LINE 6

(If additional description is necessary, use BACK of this sheet)  
 Correspondence regarding this well should be addressed to Sunray Oil Corporation  
 Address. Box 195, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
 Fred McDaniel (employee of owner) of the above-described well,  
 being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Fred McDaniel*  
 Box 195, Great Bend, Kansas  
 (Address)

SUBSCRIBED AND SWORN to before me this 10th day of October, 1944.  
*Anna Niedens*  
 Notary Public.

My commission expires May 10, 1948

Sunray Oil Co.  
Hanschild 1

Sec. 17 Twp. 15 Rge 19  
County: Ellis, Kansas

Total Depth: 3621  
Comm: 9/6/44 Comp: 9/30/44

Casing  
4 Jts. 15" pipe  
1230' 8 5/8" Pipe 1219'

Cement  
83.04' cemented with  
125 sacks  
1 sack Calcium Chloride  
500 sacks Cement  
5  
Depth: 500' Calcium Chloride

Formation:

Sand	63'
Red Sand Rock	90'
Shale & Shells	335
Sand	390
Shale & Shells	580
Sand & Shale	660
Soft Sand	760
Sand	889
Red Bed & Shells	1175
Red Rock & Shells	1208
Anhydrite	1223
Anhydrite	1230
Sand Lime	1245
Anhydrite	1250
Red Bed & Shells	1400
Shale & Shells	1900
Lime & Shale	2235
Broken Lime	2287
Broken Lime & Shale	2350
Lime & Shale	2562
Sandy Lime	2580
Lime & Shale	2620
Shale & Lime	3104
Lime	3269
Lime & Shale	3322
Lime	3406
Lime & Shale	3570
Chert	3580
Cherty Lime & Shale	3609
Sand	3617
Sand & Pt. of Iron	3621

State of Kansas )  
                          ) SS  
Russell County )

I hereby certify that the above information is true and correct to the best of my knowledge.

Subscribed and sworn to before me this 2nd day of October, 1944.

My Comm. expires 7/2/45

*Genevieve Poole*  
Notary Public

