

Notice: Fill out COMPLETELY  
and return to Conservation Division at  
the address below within  
60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 33858  
Name: J&J Operating, LLC  
Address 1: 10380 W. 179th  
Address 2: \_\_\_\_\_  
City: Bucyrus State: KS Zip: 66013 + \_\_\_\_\_  
Contact Person: John Loeffelbein  
Phone: (913) 953-7743  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 15-139-20095-00-00  
Spot Description: \_\_\_\_\_  
SE NW NW Sec. 27 Twp. 16 S. R. 17  East  West  
990 Feet from  North /  South Line of Section  
990 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: OSAGE COUNTY  
Lease Name: BINGHAM Well #: 1  
Date Well Completed: 4-8-2007  
The plugging proposal was approved on: \_\_\_\_\_ (Date)  
by: \_\_\_\_\_ (KCC District Agent's Name)  
Plugging Commenced: 4-17-2007  
Plugging Completed: 4-17-2007

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		SURFACE	12 1/4	20	0
		PRODUCTION	7 7/8	1820	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

SET 50/50 PORMIX CEMENT PLUGS. 20 SX AT 1865' - 1464', 20 SX AT 1464' - 555', 20 SX AT 555' - 250' AND 49 SX AT 250' TO SURFACE WITH GEL SPACER BETWEEN PLUGS

RECEIVED  
KANSAS CORPORATION COMMISSION

JAN 14 2013

LEGAL SECTION

Plugging Contractor License #: 33557 Name: SKYY DRILLING, LLC  
Address 1: 800 W 47TH STREET, STE 409 Address 2: \_\_\_\_\_  
City: KANSAS CITY State: MISSOURI Zip: 64112 + \_\_\_\_\_  
Phone: (816) 531-5922  
Name of Party Responsible for Plugging Fees: J&J OPERATING, LLC  
State of KANSAS County, MIAMI, ss.

\_\_\_\_\_  
(Print Name)  Employee of Operator or  Operator on above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: \_\_\_\_\_

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

bc

Conservation Division  
Finnay State Office Building  
130 S. Market, Rm. 2078  
Wichita, KS 67202-3802



Phone: 316-337-6200  
Fax: 316-337-6211  
<http://kcc.ks.gov/>

Mark Sievers, Chairman  
Thomas E. Wright, Commissioner

Sam Brownback, Governor

October 30, 2012

Jim Loeffelbein  
J & J Operating, LLC  
10380 W. 179<sup>th</sup> Street  
Bucyrus, Kansas 66013-9596

**Re: Unplugged Well(s) on Expired License #33858**

Dear Operator,

A review of Commission records shows your license expired on October 30, 2011. Attached to this letter is a list of wells that remain on your record and appear to be unplugged.

It is a violation of K.A.R. 82-3-120 for an operator with an expired license to remain in control of an unplugged well.

**Please renew your license, or transfer the above wells by filing a T-1 form with the Commission, or file a CP-1 form for each of the above wells, by November 30, 2012. Failure to do so may result in a recommendation to the Commission that it issue an Order with a monetary penalty that also obligates you to plug the well(s).**

Note that there may be additional wells on your record that appear to be plugged. If you choose to renew your license, these wells may need to be included in your certified well inventory.

Please contact me if you have any questions about the status of these wells.

Sincerely,

John McCannon  
Litigation Counsel

RECEIVED  
KANSAS CORPORATION COMMISSION

JAN 14 2013

LEGAL SECTION

33761

CONSOLIDATED OIL WELL SERVICES, LLC  
 P.O. BOX 884, CHANUTE, KS 66720  
 620-431-9210 OR 800-467-8676

TICKET NUMBER 15393  
 LOCATION Ottawa KS  
 FOREMAN Fred Mader

TREATMENT REPORT & FIELD TICKET  
 CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
4/17/07	4028	Bingham #1	27	14	17	D.S.
CUSTOMER I J Operating LLC			TRUCK #			
MAILING ADDRESS 10380 W 179th St			DRIVER			
CITY Bucyrus		STATE KS	ZIP CODE 66013	TRUCK #		DRIVER
JOB TYPE <u>Plug</u>			HOLE SIZE <u>7 1/8</u>	HOLE DEPTH <u>1865'</u>	CASING SIZE & WEIGHT	
CASING DEPTH			DRILL PIPE <u>36</u>	TUBING	OTHER <u>None</u>	
SLURRY WEIGHT			SLURRY VOL	WATER gal/sk	CEMENT LEFT IN CASING <u>Full</u>	
DISPLACEMENT			DISPLACEMENT PSI	MIX PSI	RATE	

REMARKS: Establish Circulation thru 3 1/2" drill pipe. Spot 20 sks - (50')  
 on TD. Pull to 1464' Spot 20 sks. (50') @ Pull to 555'  
 Spot 20 sks - (50') pull to 250' Fill to surface. Pull remaining  
 drill pipe + top of well w/ 49 sacks. Fill patch hole w/ 10 sks  
 + wash up. 119 sks Total 50/50 Per Mix 1 1/2 Premium Gel

*Fred Mader*

SKYE Drilling.

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5405N	1 Plug	PUMP CHARGE Cement Pump	164	164.00
5406	20 mi.	MILEAGE Pump Truck	164	66.00
5407	Minimum	Tax Mileage	510	285.00
5501C	3 1/2 hrs	Transport 505-706		350.00
5402	1865'	Casing Footage	164	335.00
1124	112 sks	50/50 Per Mix Cement		991.20
11183	600	Premium Gel		90.00
Sub Total				2957.20
Tax @ 6.3%				68.12
RECEIVED				
KANSAS CORPORATION COMMISSION				
JAN 14 2013				
LEGAL SECTION				SALES TAX ESTIMATED TOTAL

AUTHORIZATION W0# 213055

TITLE

DATE

3026.00

**CEMENTING WORK ORDER**

**CONSOLIDATED OIL WELL SERVICES, LLC**  
Phone (820) 431-9210 Chanute, Kansas 66720

DAY Tue  
DATE 4/17/2007  
Month / Day / Time

NAME OF CUSTOMER: J&J Operating LLC

LEASE # Bingham WELL # 1  
JOB DESCRIPTION: plug

PIPE SIZE ~~4 1/2~~ SIZE OF HOLE: 7 7/8

DEPTH OF WELL: 1865

TYPE OF RIG: AIR MUD

AMOUNT OF CEMENT NEEDED 119 sks 50/50 poz

% OF GEL NEEDED: 6%

MATERIALS: 112 sks poz, 600# gel  
200# gel

TRUCKS: VAC TRANSPORT

LOCATION OF JOB:  
506-FM, 164-RA, 510-KH, 505/T106-AH

ORDER TAKEN BY: Jim Green

Swilliams  
11:20:52 AM 4/23/2007

**RECEIVED**  
KANSAS CORPORATION COMMISSION  
**JAN 14 2013**  
LEGAL SECTION

33557

Skyy Drilling, L.L.C.  
800 W. 47<sup>th</sup> Street, Suite # 409  
Kansas City, Missouri 64112  
Office (816) 531-5922  
Fax (816) 753-0140

May 1, 2007

Company: J & J Operating, LLC  
10380 West 179<sup>th</sup>  
Bucyrus, Kansas 66013

Lease: Bingham – Well # 1 – Wildcat  
County: Osage  
Spud Date: April 6, 2007  
Spot: SE-NW-NW – Sec 27, Twp 16, SR 17 East  
API: 15-139-20095-0000  
TD: 1865'

4/6/07 Moved in, rigged up. Pump water, drilled rat hole, spud 12 ¼ surface at 9:30 P.M. Drilled from 0' to 49'.

4/7/07 Drilled from 49' to 212' TD. TD 12 ¼ surface @ 212, cir hole clean, tripped out 12 ¼ bit, rigged & ran 201' – 8 5/8. Cemented plug down @ 2:00 A.M. 4/8/07.

4/11/07 Started up, tripped in hole with 7 7/8 bit, drilled out approx 30' cement, under surface drilling at 4:00 P.M. Drilled from 212' to 555'.

4/12/07 Drilled from 555' to 931'.

4/13/07 Drilled from 931' to 1436'. Started mud up @ 1057'

4/14/07 Drilled from 1436' to 1575' – Top Miss Lime @ 1459' At top Miss Lime started drilling @ rig time rate.  
23 Hours Rig Time

4/15/07 Drilled from 1575' to 1755'. At 1585' tripped bit  
24 Hours Rig Time

4/16/07 Drilled from 1755' to 1865' TD  
24 Hours Rig Time  
At TD cir hole clean, tripped out drill pipe, lay down drill collars. Trip in drill pipe open end. Rig cementer to plug hole.  
Pumped 50' plug @ 1865 TD  
Pumped 2<sup>nd</sup> plug @ 1464 – 50' plug  
Pumped 3<sup>rd</sup> plug 50' – 555 Top KC  
Pumped 4<sup>th</sup> plug 250' to surface. Job complete. Rig down rig.

RECEIVED  
KANSAS CORPORATION COMMISSION

JAN 14 2013

LEGAL SECTION

CONSOLIDATED OIL WELL SERVICES, INC.  
P.O. BOX 884, CHANUTE, KS 66720  
620-431-9210 OR 800-467-8676

TICKET NUMBER 15407  
LOCATION Ottawa  
FOREMAN Alan Mader

TREATMENT REPORT & FIELD TICKET

Jim Loeffelbein 913-851-5825 CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
4-8-07	4028	Bingham #1	27	16	17	Os
CUSTOMER			TRUCK #	DRIVER	TRUCK #	DRIVER
J&J Operating			516	Alan M		
MAILING ADDRESS			164	Rick A		
10380 W 179th			370	Ken H		
CITY	STATE	ZIP CODE	195	Gary A		
Bucyrus	KS	66013				

JOB TYPE Surface HOLE SIZE 12 1/4 HOLE DEPTH 212 CASING SIZE & WEIGHT 8 5/8  
 CASING DEPTH 200 DRILL PIPE \_\_\_\_\_ TUBING \_\_\_\_\_ OTHER 10' land su  
 SLURRY WEIGHT \_\_\_\_\_ SLURRY VOL \_\_\_\_\_ WATER gal/sk \_\_\_\_\_ CEMENT LEFT in CASING YAS  
 DISPLACEMENT 12 1/2 DISPLACEMENT PSI \_\_\_\_\_ MIX PSI \_\_\_\_\_ RATE 5 bpm

REMARKS: Established rate. Pumped 12 bbl water to flush hole. Mixed & pumped 3 1/2 bbl dye marker followed by 11 sx Portland "A", 2% gel, 2% calcium, 1/4" flo-seal. Circulated dye to surface. Displaced casing with 12 1/2 bbl water. Circulated 4 1/2 bbl cement into pit closed valve.

*Alan Mader*

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
54015	1	PUMP CHARGE	164	650.00
5406	20	MILEAGE	167	66.00
5402	200'	casing footage	164	NIL
5407	min	ten mileage	195	285.00
5502C	4	80 gal		360.00
5408		weekend charge		272.20
1102	222 #	calcium		148.74
11045	106 sx	Portland "A"		1293.20
1107	28 #	Flo-seal		53.20
11183	222 #	gel		33.30
RECEIVED				
KANSAS CORPORATION COMMISSION			Sub	3161.64
JAN 14 2013				
LEGAL SECTION				
			05 6.3%	SALES TAX 96.29
				ESTIMATED TOTAL 3257.93

AUTHORIZATION W# 212934

TITLE \_\_\_\_\_ DATE \_\_\_\_\_