


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Seward County. Sec. 20 Twp. 31S Rge. 31 E (W)  
Location as "NE/CNW 1/4 SW 1/4" or footage from lines  
300' FWL and 300' FSL

Lease Owner Energy Reserves Group, Inc.  
Lease Name Stevens Trust Well No. 1  
Office Address 3613 NW 56, Okla. City, Oklahoma 73112  
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above  
Section Plot

Oil  
Date Well completed 1-10 1977  
Application for plugging filed 9-23 1980  
Application for plugging approved 9-26 1980  
Plugging commenced 10-30 1980  
Plugging completed 11-3 1980

Reason for abandonment of well or producing formation  
non-economical production  
If a producing well is abandoned, date of last production  
October 1979

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas  
Producing formation Morrow Depth to top 5449 Bottom 54 Total Depth of Well 5570  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Winfield		2700	2735	8-5/8	1444'	none
Hebner		4200	4205	4-1/2	5570	2503
Lansing		4325	4825			
Morrow		5450	5525			
Mississippian		5525				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to  
\_\_\_\_\_ feet for each plug set.

Pump 2 sx hulls and 25 sx cmt from 5454' to 5200'  
Pump 50 sx cmt from 1475' to 1315'  
Pump 25 sx cmt from 700' to 600'  
Pump 10 sx cmt from 40' to 0'  
cut off and cap 8-5/8"

STATE OF KANSAS

DEC 19 1980

12-19-80

CONSERVATION DIVISION

Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sargents Casing Pulling Service, Box 506, Liberal, KS No. 511

STATE OF Oklahoma COUNTY OF Oklahoma, ss.  
Kenneth Ray Sneed (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of  
the facts, statements, and matters herein contained and the log of the above-described well  
as filed and that the same are true and correct. So help me God.

(Signature) Kenneth R Sneed  
3613 N.W. 56th, Okla. City, OK 73112  
(Address)

SUBSCRIBED AND SWORN TO before me this 18 day of December, 19 80

[Signature]  
Notary Public.

My commission expires 2-28-82