

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-007-00316-0001

API NUMBER NA

LEASE NAME RINKE #

WELL NUMBER #14

330 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 25 TWP. 32 SRGE. 14 (E) or (W)

COUNTY BARBER

Date Well Completed 8-1-91

Plugging Commenced 7-16-91

Plugging Completed 8-1-91

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR DECKER LEASE OPERATIONS INC.

ADDRESS RR 2, Box 139A, GALVA, KANSAS 67443

PHONE# 316-654-3806 OPERATORS LICENSE NO. 3828

Character of Well S.W.D

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on August 1, 1991 (date)

by Stephen J. Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? NO If not, is well log attached? NO

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED
 STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled out
				<u>8 3/8</u>	<u>288</u>	<u>NDN</u>
				<u>7"</u>	<u>996'</u>	<u>NDN</u>

CONS. DIV. ATTL. VISIT
 WICHITA, KANSAS

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pumped down 500 lbs of ball + 165 sx 65/35 Pozmix 4 to gel, 3 to cc cement.
- Pumped down 7" x 8 3/8" Annulus with 100 sx cement. Had blow on 7" casing while pumping.
Used 265 sx 65/35 Pozmix 4 to gel, 3 to cc + 42 sx 60/40 Pozmix 6 to gel + tagged top of cement at 1160' from surface. Cement circulated out 7" x 8 3/8" Annulus - Plugging Complete Aug 1, 1991
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor BJ SERVICES License No. 648647

Address P.O. Box 4442 Houston, Texas 77210

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Decker Lease Operations, Inc.

STATE OF Kansas COUNTY OF McPherson, ss.

Decker Lease Operations Inc - Thorette Decker (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Thorette Decker

(Address) RR 2, Box 139A, Galva, KS 67443

SUBSCRIBED AND SWORN TO before me this 2 day of Oct, 1991

Merle F. Olds
 Notary Public

