

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Kingman County, Sec. 27 Twp. 27 Rge. 7W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
NE SE NW

Lease Owner Texas Oil & Gas Corp.
Lease Name Schwartz Well No. A-1

Office Address 200 W. Douglas, Suite 300, Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole)



Dry
Date Well completed 9-4- 19 81
Application for plugging filed 12-8 19 81
Application for plugging approved 12-10 19 81
Plugging commenced 2-22 19 82
Plugging completed 3-1 19 82
Reason for abandonment of well or producing formation

Dry
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. V. Leslie
Producing formation Depth to top Bottom Total Depth of Well 4350
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	250	None
				4 1/2	4389	3480

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug back at 4278
Sand from 4278 to 4245
4 sacks cement from 4245 to 4205
Ripped at 3480' Pulled and layed down
Allied pump in 15 gell 6 hull 10 gel
150 sacks common cement 3% c.c.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Clarke Corporation

STATE OF Kansas COUNTY OF Barker, ss.
(employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Elmer J. Maggert
Medicine Lodge, Mo.
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of March, 1982

Jessie Hamilton
Notary Public.

My commission expires April 4, 1982

RECEIVED
STATE CORPORATION COMMISSION

MAP
03-06-82
CONSERVATION DIVISION
Wichita, Kansas

OPERATOR: Texas Oil & Gas Corp.
 200 West Douglas
 Wichita, Kansas 67202

WELL NAME: Schwartz 'A' #1
 NE SE NW Sec. 27-27S-7W
 Kingman County, Kansas

CONTRACTOR: Slawson Drilling Company, Inc.
 200 Douglas Building
 Wichita, Kansas 67202

COMMENCED: 9/4/81

COMPLETED: 9/16/81

RTD: 4350'

SURFACE CASING: 8-5/8" set at 250' with 250 sx cement

PRODUCTION CASING: 4-1/2" set at 4349' with 150 sx cement

PROD. FILE

0' to 255' Red Bed (Surface Hole)
 255' to 435' Red Bed & Shale
 435' to 1270' Red Bed
 1270' to 1565' Shale
 1565' to 2117' Lime & Shale (Indian Cave- Waubaussee)
 2117' to 3945' Lime & Shale
 3945' to 4063' Mississippian
 4063' to 4266' Lime & Shale
 4266' Viola
 4266' to 4286' Viola
 4286' to 4350' Lime & Shale
 RTD 4350'

STATE OF KANSAS

COUNTY OF SEDGWICK

I, James C. Remsberg, of the Slawson Drilling Company, Inc. hereby
 state the above is an accurate copy of the Schwartz 'A' #1 log for
 Texas Oil & Gas Corp.

RECEIVED
STATE CORPORATION COMMISSION

DEC 10 1981

CONSERVATION DIVISION
Wichita, Kansas

James C. Remsberg
 James C. Remsberg

Subscribed and sworn to me this
 12th day of October, 1981

Mary Lou Taylor
 Mary Lou Taylor, Notary

My commission expires January 17, 1985

