

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 6/4/84  
RECEIVED  
STATE CORPORATION

FEB 13 1986

WELL PLUGGING APPLICATION FORM  
(File One Copy)

CONSERVATION  
Wichita  
7/86

API NUMBER 15-097-20,622 0000 (of this well)  
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Grüss Petroleum Management, Inc. OPERATORS LICENSE NO. 9726  
900 Building of the Southwest, 310 West Texas  
ADDRESS Midland, Texas 79701 PHONE # (915) 682-8319

LEASE (FARM) Dirks WELL NO. 1 WELL LOCATION 1710'FSL COUNTY KIOWA  
1650'FEL

SEC. 32 TWP. 28 S RGE. 18 (X) or (W) TOTAL DEPTH 4940' PLUG BACK TD 3658 (cmt ret)

Check One:

OIL WELL  GAS WELL  D & A \_\_\_\_\_ SWD or INJ WELL \_\_\_\_\_ DOCKET NO. \_\_\_\_\_

*Handwritten:* SURFACE CASING SIZE 8 5/8" SET AT 595' CEMENTED WITH 375 SACKS

CASING SIZE 4 1/2" SET AT 4924 CEMENTED WITH 425\* SACKS

PERFORATED AT 3593½ to 3598½ (tt120shts) (\*150sx Primary 275sx-3 Squeezes)

CONDITION OF WELL: GOOD  POOR \_\_\_\_\_ CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Br Plug @4883 w/ 2sx Common; Cmt retrn  
@3680; Cmt retrn @ 3658: (prev done w/KCC guidance). Suggest 11 sx Common above  
3658 and across perfs(w/ est TOC @3530')\*40sx Common across Anhydrite @1210'  
40sx Common from 630' to tie in to surf csg, and 10sx Common @40'.  
Will attempt to recover csq @± 3500' before final plugs set.

(If additional space is needed use back of form)

Discussed w/ Richard Lacey Dist 1 Dodge City on 2/12-2/13 Reports filed  
IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NO IS ACO-1 FILED? in 1981  
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Friday 2/14/86 @ 2:00pm (K&K Well Serv)

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

C.K. Morrison PHONE # (316) 788-5160(Home)

ADDRESS P.O. Drawer 707, Derby, Kansas 67037

PLUGGING CONTRACTOR Midwest Casing Pulling (Ed Eves) LICENSE NO. \_\_\_\_\_

ADDRESS P.O. Box F, Sublette, Kansas 67877 PHONE # 316, 675-8349

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: [Signature]  
(Operator or Agent)

DATE: February 13, 1986

①



JOHN CARLIN  
MICHAEL LENNEN  
MARGALEE WRIGHT  
KEITH R. HENLEY  
JUDITH A. McCONNELL  
BRIAN J. MOLINE

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary  
General Counsel

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
200 Colorado Derby Building  
202 West 1st Street  
WICHITA, KANSAS 67202-1286

THIS NOTICE

MAY 13 1986

EXPIRES

February 13, 1986  
WELL PLUGGING NOTICE

Dirks #1  
1710' FSL 1650' FEL  
Sec. 32-28S-18W  
Kiowa County

Gruss Petroleum Management, Inc.  
900 Building of the Southwest  
310 West Texas  
Midland, TX 79701

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Sincerely,

William R. Bryson, Director

Please contact the district office to review your suggested method of plugging

DIST. #1 302 West McArtor Dodge City, KS 67801 316-225-6760

five days prior to plugging the well (KAR-82-3-113).