

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-047-20.816 0000 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.) 6/88

LEASE OPERATOR Petex Petroleum Corp OPERATORS LICENSE NO. 6278

ADDRESS 1616 Glenarm, Ste. 1700 Denver, Colorado 80202 PHONE # (303) 629-1098

LEASE (FARM) Hornung WELL NO. 1 WELL LOCATION NE NE COUNTY Edwards

SEC. 33 TWP. 25 RGE. 20 (E) or (W) TOTAL DEPTH 4800 PLUG BACK TD 4740

Check One:

OIL WELL _____ GAS WELL XX D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 340 CEMENTED WITH 300 SACKS

CASING SIZE 4 1/2" SET AT 4815 CEMENTED WITH 150 SACKS

PERFORATED AT 4720' - 4722'

CONDITION OF WELL: GOOD XX POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Spot 20 sxs Cement across perms, Shoot off Casing at free point and lay down, Pump 10 sxs gel followed by 50 sxs Cmt followed by 10 sxs gel followed by 100 sxs cement down Surface Casing.
(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes _____ IS ACO-1 FILED? Yes _____
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN October 12, 1987

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Don Erickson PHONE # (303) 293-8883

ADDRESS 621 17th Street Ste. 845, Denver, Colorado 80293

PLUGGING CONTRACTOR Hembree Well Service LICENSE NO. 6907

ADDRESS 302 Sycamore, Box 458, Ness City, Kansas 67560 PHONE # (316) 792-3691

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Richard [Signature]
(Operator or Agent)

Please Mail Copy of Approved Plugging Notice to:
621 17th Street Ste. 845, Denver, Colorado 80293

DATE: 9-29-87 OCT 5 1987

①



Mike Hayden
Keith R. Henley
Rich Kowalewski
Margalee Wright
Judith A. McConnell

Governor
Chairman
Commissioner
Commissioner
Executive Director

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
200 Colorado Derby Building
202 West 1st Street
WICHITA, KANSAS 67202-1286

THIS NOTICE

JAN 5 '88

EXPIRES

October 5, 1987
WELL PLUGGING NOTICE

Hornung #1
NE NE
Sec. 33-25S-20W
Edwards County

Petx Petroleum Corporation
1616 Glenarm Street, Ste. 1700
Denver, CO 80202


Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

Please contact the district office listed below to review your suggested method of plugging five days prior to plugging the well (KAR-82-3-113).

This notice is void after ninety (90) days from the above date.

Sincerely,



Shari Feist
Director
State Corporation Commission

DISTRICT #1 302 W. McArtor, Dodge City, KS 67801 (316) 225-6760

GEARHART

COMPENSATED DENSITY COMPENSATED NEUTRON LOG

Correct copy

FILING NO. 7553-263 156453	COMPANY <u>PETA PETROLEUM</u>
	WELL <u>HORNUNG #1</u>
	FIELD <u>WILDCAT</u>
	COUNTY <u>EDWARDS</u> STATE <u>KANSAS</u>
	LOCATION <u>C-NE-NE</u>
SEC. <u>33</u> TWP <u>25S</u> RGE <u>20W</u>	OTHER SERVICES: DIL

PERMANENT DATUM <u>G.L.</u> ELEV <u>2264</u>	ELEV. KB <u>2272</u>
LOG MEASURED FROM <u>K.B.</u> <u>8</u> FT ABOVE PERM DATUM	DF <u>2271</u>
DRILLING MEASURED FROM <u>K.B.</u>	GL <u>2264</u>

Date	<u>5-30-81</u>
Run No.	<u>ONE</u>
Depth-Driller	<u>4800</u>
Depth-Logger	<u>4796</u>
Bottom logged interval	<u>4795</u>
Top logged interval	<u>350</u>
Type fluid in hole	<u>CHEMICAL</u>
Density	<u>9.1</u>
Visc.	<u>44</u>
pH	<u>9.5</u>
Fluid Loss	<u>13.6</u>
Max rec. temp. deg F.	<u>118</u> °F
Source of Samples	<u>FLOWLINE</u>
Rm @ Meas. Temp.	<u>1.3 @ 66</u> °F
Rmf @ Meas. Temp.	<u>1.0 @ 68</u> °F
Rmc @ Meas. Temp.	<u>1.5 @ 68</u> °F
Source Rmf	<u>M</u>
Source Rmc	<u>M</u>
End Circulation	<u>3:30</u>
Logger on Bottom	<u>10:20</u>
Recorded By	<u>JOHNSON</u>
Witnessed By	<u>MS. HEFFRON</u>

FIELD PRINT

Run No.	Bore-Hole Record				Casing Record			
	Level	Bit	From	To	Size	Wgt.	From	To
<u>ONE</u>	<u>Full</u>	<u>12 1/4</u>	<u>KB</u>	<u>354</u>	<u>8 7/8</u>	<u>-</u>	<u>KB</u>	<u>354</u>
<u>Two</u>	<u>Full</u>	<u>7 7/8</u>	<u>354</u>	<u>4800</u>				

CCT 5 1981

CONSERVATION DIVISION
Wichita, Kansas

FOLD HERE

MISSION