


15-007-20988-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Barber County, Sec. 9 Twp. 32 Rge. 12W E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
660' ENL & 660' FWL
Lease Owner Texas Oil & Gas Corp.
Lease Name Hough Well No. 1
Office Address 200 W. Douglas-Suite 300, Wichita, KS
Character of Well (Completed as Oil, Gas or Dry Hole) 67202
Dry Hole
Date Well completed September 5, 1980
Application for plugging filed Verbal Application 19
Application for plugging approved Verbal Approval 19
Plugging commenced September 5, 1980
Plugging completed September 5, 1980
Reason for abandonment of well or producing formation



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well William T. Owen
Producing formation Depth to top Bottom Total Depth of Well 3,520'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	327'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy rotary mud from 3,520 ft. (rotary total depth) to 340 ft. Set plug at 340 ft. and cemented with 40 sacks cement. Filled hole with heavy rotary mud from 340 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 10 sacks cement, 5 sacks cement in rat hole and 5 sacks cement in mouse hole.

Plugging operations accomplished utilizing Dowell Oil Well cementing pump truck through 4 1/2 inch drill pipe.

RECEIVED
STATE CORPORATION COMMISSION
SEP 16 1980
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Dowell Div., Dow Chemical Co.
Hwy. 281 & Santa Fe, Pratt, Kansas


STATE OF Kansas COUNTY OF Sedgwick
Dean Britting, Agent

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting
251 N. Water #10, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of September, 1980

My commission expires July 25, 1982
Elsie Willison - Notary Public.



KANSAS DRILLERS LOG

COMPANY Texas Oil & Gas Corp.

SEC. 9 T. 32 R. 12W
LOC. 660' FNL & 660' FWL

FARM Hough NO. 1

COUNTY Barber

ROTARY TOTAL DEPTH 3,520'
COMM. August 29, 1980 COMP. September 5, 1980
CONTRACTOR H-30, Inc. (Rig #5)
ISSUED September 15, 1980

CASING

10 3/4"
8 5/8" Set at 327' cemented w/300 sxs cement
5 1/2"
4 1/2"

ELEVATION 1,486' K.B.

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand, Shale and Red Bed	348'
Red Bed and Shale	638'
Shale and Red Bed	1,600'
Lime and Shale	1,790'
Shale and Lime	2,125'
Lime and Shale	2,500'
Shale and Lime	2,748'
Lime and Shale	3,200'
Shale and Lime	3,520'
Rotary Total Depth	3,520'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Dean Britting
Dean Britting

RECEIVED
STATE CORPORATION COMMISSION
SEP 16 1980
CONSERVATION DIVISION
Wichita, Kansas

State of Kansas)
) ss:
County of Sedgwick)

Subscribed and Sworn to before me a Notary Public in and for said county and state this 15th day of September, 1980.

WILLIS
NOTARY
1980

Elsie Willison
Elsie Willison - Notary Public

My Commission Expires:

July 25, 1982