


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

15-155-01652-0000 Form CP-4
WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Reno County, Sec. 20 Twp. 22S Rge. 8 (E) (W) X
Location as "NE/CNW/SW" or footage from lines C NE NW
Lease Owner Mull Drilling Company
Lease Name Grover Well No. 1
Office Address 1625 Wichita Plaza Building Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19____
Application for plugging filed 12-28-67 19____
Application for plugging approved 12-28-67 19____
Plugging commenced 1-16-68 19____
Plugging completed 1-23-68 19____
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well _____
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well PB 3584 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|-------|--------|------------|
| | | | | 8 5/8 | 220 | None |
| | | | | 4 1/2 | None | 2930 |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Moved in. Rigged up.

Cleaned out cellar. Sanded to 3500'. Dumped 4 sacks of cement. Working pipe at 2930'.

Working pipe. Circulating. Spotted 70 bbl of oil.

Working pipe. Pulling pipe.

Bailed hole down to 220'. Build 10' rock bridge with 20 sacks. Mudded 40'. Build 10' rock bridge. Capped well with 10 sacks.

RECEIVED
STATE CORPORATION COMMISSION
JAN 29 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Forbes Casing Pulling, Inc.
Address P. O. Box 221 Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Barton, ss.
J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes
P. O. Box 221 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 25 day of January, 1968

My commission expires May 27, 1969

Notary Public.

15-155-01652-0000

ROTARY DRILLERS LOG

COMPANY: Mull Drilling Co., Inc. Et Al
Wichita, Kansas

ROTARY DRILLING COMMENCED: 1/15/62

CONTRACTOR: Mull Drilling Co., Inc.
Wichita, Kansas

ROTARY DRILLING COMPLETED: 1/23/62

CASING RECORD: 220' of 8 5/8" csg. w/175 sz
3604' of 4 1/2" csg. w/125 sz

LOCATION: GROVER #1
C NE NW 20-22S-6W
Reno County, Kansas

(Figures indicate bottom of formation - measurements from top of Rotary Bushing)

| | |
|-------|--------------------------|
| 600' | Red Bed |
| 1200' | Shale & Shells |
| 3578' | Lime & Shale |
| 3582' | Miss. Lime |
| 3605' | Kinderhook - total depth |


I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

MULL DRILLING COMPANY, INC.

Delbert J. Costa
Delbert J. Costa, Geologist

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Subscribed and sworn to before me this 5th day of February, 1962



Mrs. M. Miller
Notary Public

RECEIVED
STATE OF KANSAS COMMISSIONER

DEC 29 1967
12-29-67
CONSERVATION DIVISION
Wichita, Kansas