


STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
P. O. BOX 17027
WICHITA, KANSAS 67217

FORM CP-4

WELL PLUGGING RECORD



Locate well correctly on above Section Plot

Edwards County. Sec. 33 Twp. 25S Rgs. 20W (E) (W)
Location as "NE/CNW/SE" or footage from lines. SE SE SE
Lease Owner Thornton E. Anderson
Lease Name Birzer Well No. 1
Office Address Suite 746, 300 W. Douglas, Wichita, Ks. 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 2-5 1975
Application for plugging filed 2-20 1975
Application for plugging approved ? 19
Plugging commenced 2-5-75, 2:00 A.M. 19
Plugging completed 2-5-75, 6:00 A.M. 19
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well ?
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug at 300' with 35 sacks of cement
Plug at 40' with 15 sacks of cement
Plug with 2 sacks of cement in rat hole

RECEIVED
STATE CORPORATION COMMISSION
MAR 21 1975
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Gabbert - Jones, Inc.
Address 830 Sutton Place, Wichita, Ks. 67202

STATE OF Kansas COUNTY OF Sedgwick ss.
(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Thornton E. Anderson
(Address) _____

SUBSCRIBED AND SWORN TO before me this 20th day of March, 1975

My commission expires _____

FLO DUNCAN
STATE NOTARY PUBLIC
SEDGWICK COUNTY, KANSAS
Comm. Expires June 23, 1978

Notary Public.

Please to
mail to
State Corp. Comm.

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

RECEIVED
STATE CORPORATION COMMISSION

FEB 14 1975

CONSERVATION DIVISION
Wichita, Kansas

Birzer #1
JE # SE-SE Sec 33-25S-20W
Edwards County Kansas

Commenced: 1-23-75

Completed: 2-5-75

OPERATOR: THORNTON ANDERSON

Depth	Formation	Remarks
From to		
0 135	Sand	
135 335	Clay-Sand	Ran 8 jts of used 28#
335 704	Redbed	8 5/8" csg set @ 331' Cemented
704 722	Anhy	w/225 sks Common 2% Gel
722 873	Shale	3% CC PD @ 4:30 a.m. 1-24-75
873 1279	Shale-Sand	
1279 1307	Anhy	
1307 1527	Redbed	
1527 2219	Shale-Redbed	
2219 2350	Shale-Lime-Stks	
2350 2453	Shale- Lime	
2453 3932	Lime-Shale	
3932 4735	Lime	
4735 4735		DRY & ABANDONED

I, James @. Sutton II, certify this is a correct copy of the Drillers' Log for the well drilled C-SE-SE Sec 33-25S-20W Edwards County Kansas to the best of my knowledge and belief.

James S. Sutton II
JAMES S. SUTTON II

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 10th day of February 1975, personally appeared James S. Sutton II to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

Marjorie Hall
MARJORIE HALL-NOTARY PUBLIC



My Commission Expires: 11-29-75